

SITE PLAN REVIEW REGULATIONS

FOR THE
TOWN OF RAYMOND, NH




Table of Contents

| | |
|---|-----------|
| ARTICLE I – PURPOSE AND AUTHORITY | 1 |
| 1.01 AUTHORITY | 1 |
| 1.02 PURPOSE..... | 1 |
| ARTICLE II – DEFINITIONS..... | 1 |
| ARTICLE III – PROCEDURES..... | 5 |
| 3.01 SITE PLAN REVIEW REQUIRED | 5 |
| 3.02 CHANGE OF USE REVIEW | 5 |
| 3.03 APPLICATION PROCEDURES..... | 5 |
| 3.04 FEES | 7 |
| 3.05 PERFORMANCE AGREEMENT | 8 |
| 3.06 ADDITIONAL ADMINISTRATIVE EXPENSES AND SPECIAL STUDIES | 8 |
| 3.07 OFF-SITE IMPROVEMENTS..... | 8 |
| 3.08 BLASTING | 9 |
| ARTICLE IV – GENERAL REQUIREMENTS..... | 10 |
| 4.01 COMPLIANCE WITH REGULATIONS | 10 |
| 4.02 GENERAL REQUIREMENTS..... | 10 |
| 4.03 HIGHER STANDARDS SHALL APPLY | 12 |
| 4.04 SUITABILITY OF LAND..... | 12 |
| 4.05 CONSTRUCTION OF IMPROVEMENTS..... | 12 |
| ARTICLE V – PLAN & SUBMISSION REQUIREMENTS..... | 13 |
| 5.01 GENERAL..... | 13 |
| 5.02 EXISTING DATA AND INFORMATION | 13 |
| 5.03 SITE PLAN AND INFORMATION..... | 15 |
| 5.04 ADDITIONAL INFORMATION..... | 17 |
| 5.05 GROUNDWATER PROTECTION | 18 |
| ARTICLE VI – REVIEW STANDARDS | 19 |
| 6.01 ACCESS DESIGN..... | 19 |
| 6.02 STREET CONSTRUCTION STANDARDS..... | 20 |
| 6.03 TRAFFIC IMPACT ANALYSIS..... | 21 |
| 6.04 CONSTRUCTION SITE STORMWATER RUNOFF CONTROL: EROSION AND SEDIMENT CONTROL..... | 22 |
| 6.05 UTILITIES | 26 |
| 6.06 PARKING STANDARDS..... | 26 |
| 6.07 PARKING AREAS AND ACCESS DRIVES | 29 |
| 6.08 LOADING SPACE STANDARDS | 29 |
| 6.09 FIRE PROTECTION | 30 |

| | | |
|---|---|-----------|
| 6.10 | LANDSCAPING AND SCREENING | 31 |
| 6.11 | POST CONSTRUCTION STORMWATER MANAGEMENT STANDARDS | 32 |
| 6.12 | OTHER INFRASTRUCTURE | 43 |
| 6.13 | OTHER CRITERIA | 44 |
| 6.14 | TRAFFIC MARKINGS | 45 |
| ARTICLE VII – ADMINISTRATION AND ENFORCEMENT..... | | 46 |
| 7.01 | PERFORMANCE AGREEMENT AND GUARANTEE | 46 |
| 7.02 | MAINTENANCE BOND..... | 47 |
| 7.03 | INSPECTION ESCROW | 47 |
| 7.04 | PRE-CONSTRUCTION CONFERENCE..... | 47 |
| 7.05 | PROPER INSTALLATION OF IMPROVEMENTS | 47 |
| 7.06 | RELEASE OR REDUCTION OF PERFORMANCE BOND | 48 |
| 7.07 | OCCUPANCY..... | 49 |
| 7.08 | WAIVERS | 49 |
| 7.09 | PENALTIES AND FINES | 50 |
| 7.10 | OTHER REGULATIONS..... | 50 |
| 7.11 | VALIDITY | 50 |
| 7.12 | ADOPTION & AMENDMENT HISTORY | 50 |
| Appendix I - Change of Use Review | | 51 |
| Appendix II - Site Plan Review Fees are posted at Town Hall..... | | 52 |
| Appendix III - Site Plan Checklist | | 53 |

ARTICLE I – PURPOSE AND AUTHORITY

1.01 AUTHORITY

Pursuant to the authority vested in the Town of Raymond Planning Board by the voters of the Town on March 12, 1983, and in accordance with New Hampshire Revised Statutes Annotated (NH RSA) 674:44, the Planning Board does hereby adopt the following Regulations for the governing of the review of non-residential site plans, the development of multi-family dwelling units, and changes of use. These Regulations shall be entitled the "Site Plan Review Regulations for the Town of Raymond."

1.02 PURPOSE

The purpose of the Site Plan Review Regulations is to provide for the orderly development of the Town of Raymond, and to promote the public health, safety, convenience, and welfare of its residents.

ARTICLE II – DEFINITIONS

2.01 DEFINITIONS

In general, words and terms used in these Regulations shall have their customary dictionary meanings. Definitions described in the most current Town of Raymond Zoning Ordinance shall apply herein. For the purpose of these Regulations, words used within the Site Plan Review Regulations are defined as follows:

01 ABUTTER: Any person whose property is located in New Hampshire and adjoins or is directly across the street or stream from the land under consideration by the local land use board. For purposes of receiving testimony only, and not for purposes of notification, the term "abutter" shall include any person who is able to demonstrate that his land (or access via a water body or lake or anyone who's property) will be directly affected by the proposal under consideration. For purposes of receipt of notification by a municipality of a local land use board hearing, in the case of an abutting property being under a condominium or other collective form of ownership, the term abutter means the officers of the collective or association, as defined in RSA 356-B:3, XXIII. For purposes of receipt of notification by a municipality of a local land use board hearing, in the case of an abutting property being under a manufactured housing park form of ownership as defined in RSA 205-A:1, II, the term "abutter" includes the manufactured housing park owner and the tenants who own manufactured housing which adjoins or is directly across the street or stream from the land under consideration by the local land use board. For purposes of receipt of notification by a municipality in the case of a local land use hearing, "abutter" means all affected towns and their regional planning commission(s) in the case of the development having regional impact, as determined by the planning board utilizing the criteria set forth in RSA 672:3.

02 APPLICANT: The individual(s) or corporation who petitions the Planning Board for the review and approval of the Site Plan application. If the applicant is not the owner of record, a notarized letter of permission shall be required.

- 03 APPROVAL:** Formal recognition by the Planning Board certified by written endorsement on the plan, that the plan submission meets the requirements of the Site Plan Review Regulations and has been approved by the Planning Board providing that all subsequent conditions are demonstrated to have been met.
- 04 BOARD:** The Planning Board of the Town of Raymond.
- 05 DESIGN REVIEW TEAM:** Shall be comprised of those agents of the Planning Board designated to review the site plans prior to the submission to the planning board and at any time the Planning Board may choose to refer an applicant back to the Design Review Team.
- 06 COMPLETED APPLICATION:** A final Site Plan and application form submitted with all other information and materials required by the Board to make an informed decision, plus the required site plan review fees. **(See and complete the Site Plan Regulations Checklist)**
- 07 DEVELOPMENT:** The construction of improvements on or off a tract or tracts of land which shall include the enlargement of the structure, changes of use or physical changes to the site to accommodate the intended use.
- 08 DISTURBED AREA:** That portion of the Site Plan that is altered due to construction of streets, roadways, parking areas, utilities, buildings or other physical improvements including earth excavation, removal or alteration.
- 09 ENLARGEMENT:** The increase in size or the expansion of any structure or appurtenance whether said appurtenance exists alone or in service of a structure or other appurtenance.
- 10 ENGINEER or SURVEYOR:** The duly designated and legally recognized engineer or licensed surveyor of the applicant, as may be pertinent to the actual services to be performed in accordance with the provisions of Chapter 310-A, sections 2- 27 (engineer) and sections 53-74 (surveyor) of the New Hampshire Revised Statutes Annotated.
- 10 IMPROVEMENT:** Refers to all work required to construct the proposed development including, but not limited to site grading, landscaping, utility installation, water, sewer, electric, drain, telephone, etc. and their appurtenances, roadways, parking lots, drives, buildings, fencing, signs, etc.; meaning and intending to include all the work necessary to construct the development as agreed to and shown on the approved plans, including entire on- and off-site improvements.
- 11 INDIVIDUAL WASTE DISPOSAL SYSTEM:** See also “Non-Public or Individual Waste Disposal System.”

- 12 INDIVIDUAL WATER SUPPLY SYSTEM:** See also “Non-Public or Individual Water Supply System.”
- 13 LOT:** A piece or parcel of land occupied or intended to be occupied by a principal building or group of buildings and accessory buildings, or utilized for a principal use or uses accessory or incidental to the operation thereof, together with such open spaces as required by the Zoning Ordinance and having frontage on a public street or private way or right-of-way, intended to be separately owned, rented or otherwise used as a unit.
- 14 MASTER PLAN:** Means the Town of Raymond Master Plan, as may be amended from time to time.
- 15 MULTI-FAMILY:** A residential building designed for and occupied by three or more families, regardless of the type of ownership, such as, but not limited to condominiums, apartment or other common wall or row-type housing units of the same type.
- 16 NON-PUBLIC or INDIVIDUAL WASTE DISPOSAL SYSTEM:** Any treatment system, other than a public sewer, which receives sewage or otherwastes.
- 17 NON-PUBLIC or INDIVIDUAL WATER SUPPLY SYSTEM:** Any system, other than the municipal system, providing potable water.
- 18 PERFORMANCE AGREEMENT:** An agreement executed by the Planning Board and the Applicant that includes the Conditions of Approval of the Site Plan and the improvements to be bonded, along with the estimated costs and the anticipated time of completion of the improvements.
- 19 PLANNING BOARD:** The Raymond Planning Board, as established in accordance with NH RSA 674:1-2.
- 20 PUBLIC SEWER:** Any publicly owned pipe or conduit designed to receive and convey sewage or other wastes to a municipally owned and operated treatment facility.
- 21 SEASONAL HIGH-WATER TABLE:** Means and includes the upper limit of the ground water in a soil which becomes seasonally saturated with water.

- 22 SHORELAND PROTECTION AREA:** is an area of land within seventy-five (75) feet of the seasonal highwater mark of any river, brook, lake or intermittent or perennial stream.
- 23 SITE PLAN:** The development plan for one or more lots on which is shown the existing and proposed conditions of the lot, including topography, vegetation, drainage, flood-plains, wetlands, and waterways; landscaping and open spaces; walkways; means of ingress and egress; circulation; utility services; structures and buildings; signs and lighting; berms, buffers and screening devices; surrounding development; and any other information that reasonably may be required in order for an informed decision to be made by the Planning Board.
- 24 STREET:** Means and includes such ways as alleys, avenues, boulevards, highways, roads, streets, and other rights-of-way excluding driveways per NH 674:13. The term "Streets" shall also apply to areas on any plans designated as street, roads, lanes, etc. A street is a public or private way intended to provide vehicular movement and which may or may not be continuous.
- 25 SUBDIVISION:** The division of the lot, tract or parcel of land into two or more lots, plats, sites or other divisions of land for the purpose, whether immediate or future, of sale, rent, lease condominium conveyance, or building development. It includes re-subdivision and when appropriate to the context, relates to the process of subdividing or to the land or territory subdivided. The division of a parcel of land held in common and subsequently divided into parts among the several owners shall be deemed a subdivision under this definition (NH RSA 674:14).
- 26 SURVEYOR:** See also "Engineer or Surveyor."
- 27 TECHNICAL REVIEW COMMITTEE:** Shall be comprised of those agents of the Planning Board that consists of the Planning and Development Department, the Building Inspector/Code Enforcement Officer, the Public Works Director, the Fire Chief, Assistant Fire Chief, and the Chief of Police or any designees appointed by the respective members. **The information received from the Technical Review Committee is advisory only!**
- 28 TOWN:** The Town of Raymond, New Hampshire.
- 29 TOWN ENGINEER:** The duly designated engineer for the Town of Raymond.
- 30 WETLANDS:** As defined per RSA 482-A:2 X. "an area that is inundated or saturated by surface water or groundwater at a frequency and duration sufficient to support, and that under normal circumstances does support, a prevalence of vegetation typically adapted for life in saturated soil conditions".
- 31 Wetland Buffer/Set Back:** Means a designated area contiguous or adjacent to a wetland that is required for the continued maintenance function and ecological stability of the wetland.

ARTICLE III – PROCEDURES

3.01 SITE PLAN REVIEW REQUIRED

The Planning Board shall require site plans to be submitted to it for review by any applicant seeking any of the following:

- 01** The construction of any new non-residential use;
- 02** The enlargement of any existing non-residential use which occasions development of the site;
- 03** The construction of any new multi-family dwellings;
- 04** The construction or conversion of any multi-family dwellings, other than one- and two-family dwellings, or non-residential use in which development of the site is contemplated or required by virtue of any other Town Ordinance or State Regulation or decision of the Town’s Zoning Board of Adjustment;
- 05** The enlargement of any existing multi-family use resulting in other than one- and two-family dwellings, which occasions development of the site;
- 06** The change within a structure from one permitted use to another, non-residential use or multi-family use other than one- and two-family dwellings, which will occasion development of the site including, but not limited to improvement or alteration to the site required by virtue of any other Town or State Ordinance, Statute or Regulation;
- 07** The Planning Board may, at its discretion, waive this requirement if there is no anticipated impact on traffic, off-street parking, drainage, municipal services or the surrounding neighborhood at a duly noticed public hearing.

3.02 CHANGE OF USE REVIEW

In instances where a change of use does not require a site plan, a change of use review may still be required as outlined in Appendix I. The final decision on whether to require a site plan or a change of use shall be made by the Board.

3.03 APPLICATION PROCEDURES

- 01 PROCESS/AUTHORITY:** A completed application shall include all requirements of Articles IV and V of these Regulations and be on forms supplied by the Board. The completed application, plans and fees are to be submitted to the Planning and Development Department. Upon receipt of the application, the Planning and Development Department will begin processing it following the procedure outlined in Article III, Section 3.03.2 of these Regulations. **(See and complete the Site Plan Regulations Checklist)**

02 GENERAL PROCEDURES: Prior to the submission of a site plan, it is strongly recommended that an applicant meet with Planning and Development Department staff. An applicant may also request to informally discuss plans with the Planning Board. Any meeting with the Planning Board will require formal notice in accordance with Article III, Section 3.03.05, unless the discussion is conceptual in nature and not about a specific parcel of land.

Upon submission of an application to the Planning and Development Department, once all required fees have been paid, upon receipt of a successful Zoning Determination, the application will be scheduled for a public hearing with the Planning Board to review the technical aspects of the plan.

Once an applicant appears before the Planning Board, the Planning Board shall determine whether the applicant has submitted an application which is complete for purposes of review. **(See and complete the Site Plan Regulations Checklist)** An initial presentation will then be allowed, and, upon completion, the Planning Board will make a determination as to whether or not a project has regional impact, consistent with RSA 36:54 through 58. If the Board determines that a project is one of regional impact, then it shall follow the process outlined in RSA 36:57. Once the process for regional impact is completed, the Planning Board will resume its review of the application.

03 CERTIFICATION BY DESIGN PROFESSIONALS REQUIRED:

The following shall govern the preparation and certification of the plans and studies submitted by applicants for site plan approval:

- a. A New Hampshire Licensed Land Surveyor shall prepare, sign, and seal the existing condition plan.
- b. A New Hampshire Licensed Professional Engineer shall prepare, sign, and seal all plan where grading, drainage and utility information is proposed, including stormwater management plans.
- c. Landscape plans shall be prepared by a New Hampshire Licensed Landscape Architect who shall sign and seal the landscape plan(s).
- d. Architectural elevations shall be signed or sealed by a New Hampshire Licensed Architect, or a New Hampshire Licensed Professional Engineer, as allowed by the State of New Hampshire professional licensing boards.
- e. Where wetland boundaries are required to be delineated, the delineation shall be performed by a New Hampshire Certified Wetland Scientist, who shall sign and seal the plan upon which the wetland boundaries are mapped.
- f. Where soils are required to be identified, classified, and delineated, the identification, classification, and delineation shall be performed by a New Hampshire Certified Soil Scientist, who shall sign and seal the plan upon which the soils are mapped.

- 05 BOARD ACTION:** The Planning Board shall act on the application in accordance with NH RSA 676:4.
- 06 PUBLIC HEARING AND NOTICE:** Before taking action on a site plan, the Planning Board shall hold a public hearing thereon. The applicant and abutters shall be sent notice of the public hearing via certified mail not less than ten days before the date fixed for the hearing. Additionally, notice of the public hearing shall be posted in two public places stating the time, date and place of such hearing, along with a brief description of the location(s) of the proposed site plan. Publication of such notice shall be advertised in a newspaper of general circulation in the Town of Raymond not less than ten days before the date fixed for the hearing. Associated costs, mailing, publication, etc. related to the hearing shall be paid by the applicant.
- 07 ABANDONMENT AND RE-SUBMISSION:** A plan shall be considered to have been abandoned by the applicant if he/she has not complied with the Performance Agreement, bond or escrow requirements or any other condition of approval established by the Planning Board within two years after the date of conditional approval. The applicant may be granted an extension by the Board upon written application and for reasons deemed adequate by the Board. An abandoned plan shall require a complete re-submission for new consideration by the Board.
- 08 CHANGE OF DESIGN AND IMPROVEMENTS:** If, at any time before or during the construction of the required improvements, it is demonstrated that unforeseen conditions make it necessary or preferable to modify the location or design of such required improvements, the Planning Board shall authorize changes, provided these changes are within the spirit and intent of the Board's approval, and do not extend to the modification or substantial alteration of the function of any improvements required by the Board. The Board shall authorize a change only after an amended site plan or "as-built" site plan has been submitted for review by the Board at a properly noticed public hearing. No changes, erasures, modifications or revisions shall be made on any site plan after approval has been given by the Board and endorsed in writing on the plan, except as herein provided.

3.04 FEES

In order for an application for Site Plan Review to be considered complete, it shall be accompanied by a check made out to the Town of Raymond, NH in an amount sufficient to cover the application fees as outlined on the Site Plan Review Application, as well as in Appendix II of these regulations, entitled Site Plan Review Fees. A second check, also made out to the Town of Raymond, shall be provided to establish a Planning Escrow account, as also outlined in the Appendix II.

The Board requires that an Inspection Fee be paid by the applicant into an escrow account before granting final approval and building permit(s) are issued. This inspection fee is based upon 4%¹ of the Town Engineer's approved improvement bond amount. This fee is not required for the application to be considered complete.

3.05 PERFORMANCE AGREEMENT

As a condition of the Planning Board's approval of a Site Plan, the Board shall require the applicant to execute a Performance Agreement within thirty days of receiving a conditional approval. This document shall outline the understanding of the Board and the applicant as to the terms and conditions of approval. It shall also include the improvements that require bonding as well as the bond amount for each improvement. The Town Engineer shall concur with the accuracy of the bond¹ amount. The Performance Agreement shall be prepared by the Board and its Legal Counsel if needed with the costs of preparation being borne by the applicant as provided by NH RSA 676:4, I(g).

3.06 ADDITIONAL ADMINISTRATIVE EXPENSES AND SPECIAL STUDIES

Reasonable fees in addition to fees previously noted may be imposed by the Planning Board to cover its administrative expenses and the cost of special investigative studies, review of documents and other matters which may be required as part of the Site Plan Application.

3.07 OFF-SITE IMPROVEMENTS

Where the impact of the proposed development is such that will require off-site improvements, the Planning Board shall require the applicant to mitigate said impact.

¹ Estimates for all improvements shall be provided by the Applicant for review and approval by the Raymond Public Works Director or his designee. These estimates will be utilized to establish an inspection escrow account (equal to 4% of the estimated cost of improvements), which must be in place with the Town of Raymond prior to the start of any site work. Additionally, these estimates will be used as the basis for computing the Surety/Performance Bond to be provided by the Applicant in favor of the Town of Raymond prior to the issuance of a Certificate of Occupancy by the Raymond Code Enforcement Officer. Surety/Performance Bond values shall be based upon the value of unfinished work at the time of the issuance of a Certificate of Occupancy, plus a 10% contingency.

3.08 BLASTING

If a project is known to require the blasting of materials, applicant shall so indicate in the application and certify that all blasting operations shall conform to NH RSA 158, along with the rules and regulations for Explosives promulgated by the Division of State Police, NH Department of Safety. If blasting is found to be necessary during construction of the site, then the applicant shall conform to the blasting requirements herein.

01 Local Blasting Permit Required

- (a) After review by the Planning Board for compliance with applicable regulations and conditions, blasting permits are issued and administered by the Raymond Fire Chief or designee. Blasters shall be responsible to pay local blasting permit fees, as may be revised from time to time by the Board of Selectmen.

02 Additional Minimum Requirements for Blasting

- (b) In recognizing that blasting for project sites can be intense and frequent for short-term projects, the Planning Board will require the Applicant to conduct, at a minimum, pre-blast surveys on all structures and wells not controlled by the applicant within 200 feet of the blast site. Depending on the scope and intensity of proposed blasting, the Planning Board may increase this distance, in accordance with recommendations it receives from a qualified professional selected by the Planning Board at the applicant's expense. The applicant shall provide a detailed record of each survey to the Planning Board for review and the Fire Chief or their designee and the Planning and Development Department, for placement in the project file. Applicant shall be responsible for providing updated information during the course of site development.

ARTICLE IV – GENERAL REQUIREMENTS

4.01 COMPLIANCE WITH REGULATIONS

No site improvements, utility construction, or building construction shall be started until a site plan, prepared in accordance with these Site Plan Review Regulations, has been approved by the Planning Board and other appropriate permits have been issued.

All non-residential and multi-family residential site plans shall conform to all local, State and Federal Regulations and guidelines including, but not limited to Town of Raymond Zoning Ordinance, including the Raymond Floodplain Development Ordinance, Building Code, Town of Raymond Subdivision Regulations, Multi-Family and Non-Residential Site Plan Review Regulations, Town of Raymond Water Department Regulations, Driveway Regulations and Town of Raymond Fire Department Regulations.

4.02 GENERAL REQUIREMENTS

In reviewing site plans, the Planning Board shall take into consideration the Master Plan, including the Open Space Plan, the public health, safety and general welfare, the comfort and convenience of the general public, and as a condition of approval may require such modifications of the proposed site plan as it deems necessary to comply with the spirit as well as the letter of these Regulations. The Board shall take into account the following objectives:

- 01** Safe, adequate and convenient vehicular and pedestrian traffic circulation both on- and off-site. The following aspects of the site plan shall be evaluated to determine the conformity of the site plan to this standard:
 - a. The effect of the proposed development on existing and future traffic conditions on abutting streets;
 - b. The number, locations and dimensions of vehicular and pedestrian entrances, exits, drives and walkways;
 - c. The visibility in both directions of all exit points of the site and the visibility of a vehicle entering the site to the driver of a vehicle traveling on the street;
 - d. The locations, arrangement and adequacy of on- and off-street parking facilities;
 - e. Interconnection of parking areas via access drives within and between adjacent lots in order to provide maximum efficiency and development potential, minimize curb cuts and encourage safe and convenient traffic circulation;
 - f. The location, arrangement and adequacy of truck loading and unloading facilities;
 - g. Patterns of vehicular and pedestrian circulation, both within the boundaries of the development and in relation to the adjoining street and sidewalk system;

- h. The location, arrangement and adequacy of landscaping, boarding, parking and loading facilities.

02 The protection of environmental quality and the preservation and enhancement of property values. The following aspects of the site plan shall be evaluated to determine the conformity of the site plan to this standard:

- a. The location, height and materials of walls, fences, hedges and plantings so as to ensure harmony with adjacent development, screen parking and loading areas and conceal storage areas, utility installations and other such features;
- b. The prevention of dust and erosion through the planting of ground cover or installation of other surfaces;
- c. The preservation of natural amenities and major natural and man-made features of the site such as wetlands, highly erodible areas, historic structures, major trees and scenic views;
- d. The provision of adequate storm and surface water drainage facilities to properly drain the site;
- e. The provision of adequate water and wastewater facilities to properly service the site;
- f. The protection of residential abutters against public health and safety concerns, including but not limited to groundwater contamination, undue noise, glare, unsightliness or other nuisance detrimental to property value.

03 A Community Impact Analysis shall be required for all site plan review applications. The Community Impact Analysis shall, at a minimum, completely describe the proposed use and shall include a description of how the proposed activity, both during and following construction, will impact traffic, parking and circulation, storm drainage, all utilities, infrastructure, schools, noise, the Town's fiscal condition and other community services. The Community Impact Analysis shall be based on the experience of a similar or related type of business. The extent of the Community Impact Analysis shall be commensurate with the potential impact of the proposed activity. The Planning Board may reject a Community Impact Analysis that does not adequately address all relevant issues. As a part of its review of the Community Impact Analysis, the Planning Board may require technical assistance from an outside consultant or expert in the field. Cost of such review shall be borne by the applicant in accordance with Article III, Section 3.06 of these Regulations, and NH RSA 676:4, T(g). The description of the proposed use furnished by the applicant in the Community Impact Analysis may form the basis of future change-of-use determinations.

04 In acting upon any site plan, the Planning Board shall consider the recommendations of the Technical Review Committee, the Conservation

Commission and other Town agencies or outside specialists with whom it consults.

- 05 These Regulations shall be interpreted as minimum requirements and compliance with these minimum requirements in no way obligates the Planning Board to approve any particular application solely on that basis.
- 06 The Planning Board will consider all aspects of an application before rendering its decision. This will include study of all site design and technical aspects of the proposal, as well as consideration of the impact of the development on the open space, wildlife habitat, surface water and groundwater, and other natural resources, local traffic patterns, and available public utilities, services and municipal resources.

4.03 HIGHER STANDARDS SHALL APPLY

If any other provision of Town, State or Federal Law relates to any matter covered herein, the Regulation providing the highest standard shall apply.

4.04 SUITABILITY OF LAND

Land unsuitable for development due to the presence of poorly and very poorly drained soils, flood hazard, steep slopes or other conditions constituting a danger to health, safety or the environment; or contrary to the purpose of these Regulations and the Master Plan shall not be approved for development unless the applicant presents satisfactory evidence or data to the Planning Board establishing that the methods proposed to overcome any such conditions are adequate.

4.05 CONSTRUCTION OF IMPROVEMENTS

- 01 No construction or improvements shall be made until approval is granted by the Planning Board, and the appropriate inspection escrows are established with the Town of Raymond.
- 02 No building permits shall be issued by the Code Enforcement Officer until adequate site bonding has been established and received by the Public Works Director.
- 03 No site and/or building occupancy shall be allowed until all site and building safety features have been provided.

ARTICLE V – PLAN & SUBMISSION REQUIREMENTS

5.01 GENERAL

- 01** Prior to the submission of the site plan, the applicant or his agent may submit a (Conceptual Plan) sketch showing any preliminary information to the Planning Board for discussion purposes only.
- 02** In order to meet the formal submission requirements of these Regulations, the applicant or his/her authorized agent shall submit the following in hard copy and electronic copy:
 - a. Completed Site Plan Review Application Form;
 - b. Notarized Letter of Authorization from the applicant's agent granting permission for representation;
 - c. Twelve (12) full-size sets of the site plan;
 - d. Six (6) 11 x 17 sets of the site plan, and a complete plan set in PDF format (these do not have to be submitted until the application is scheduled to go before the Planning Board); these copies must be submitted into the Planning and Development Department at least twenty-one days prior to the Planning Board meeting;
 - e. Payment of all applicable application fees in accordance with the Site Plan Review Fee Schedule located in Appendix II of these Regulations;
 - f. Funds to establish a Planning Escrow Account in accordance with the Site Plan Review Fee Schedule located in Appendix II of these Regulations;
 - g. Any additional information and supporting data the Planning Board will need to review the application.
 - h. Completed site plan review checklist.

5.02 EXISTING DATA AND INFORMATION

The following information shall be provided on the plan:

- 01** A separate sheet, clearly showing the site location relative to the surrounding road system and abutting zoning districts within 1,000 feet of the site. Such plan will consist of the Raymond tax map sheet upon which a site is located, overlaid on a topographical map, utilizing recent aerial photography found on NH GRANIT or other acceptable mapping sources.
- 02** Location of site, tax map, and lot number, current name(s) and address(es) of the owner(s) of record, abutting landowners, holders of easements, and the name, business address, seal and signature of all licensed professionals in accordance with NH RSA 310-A (from all owners listed on deeds of the affected properties);

- 03** Name(s) and address of person(s) of firm preparing the plan(s) or 3rd party consultants, the scale of the plan (1" = 20' up to 1" = 50' graphic scale), north arrow and date of survey. Name(s) and address of person(s) or firm or 3rd party consultants preparing any additional data and information, if different from the preparer(s) of the plan.
- 04** The boundary lines of the area included in the site, including distance and bearings of the lines, dimensions and the lot area, prepared and stamped by a Licensed New Hampshire Land Surveyor.
- 05** The existing slopes, drainage systems, structures and topographic contours, at intervals not exceeding two feet. Spot elevations should be shown where slope is less than 2%. All existing topographic contours to be represented with thin, light dashed lines. Topography may be derived from aerial photography or Lidar in non-developable areas. Areas being developed shall be obtained through field survey only. All G land should be specified.
- 06** Locations and widths of adjacent streets, buildings and drives within 200 feet of the site boundaries.
- 07** The shape, size, height and location of existing structures located on the site and within two hundred feet of the site boundaries.
- 08** Historic and Natural features including but not limited to streams, marshes, lakes or ponds, water courses, water bodies, wetlands, 50-year floodplain and a 100-year floodplain, or any observations that may be on record due to recent floods, ledges, boulder areas, steep slopes greater than or equal to 25% grade, and existing wooded areas. Manmade features including, but not limited to existing roads and structures. The plan shall indicate which of such features are to be retained and which are to be altered or removed.
- 09** Use of abutting properties shall be identified.
- 10** The size, location, elevation and slope of all existing public and private utilities, water mains, culverts, underground structures and all existing landscaping. This shall include the location and size of existing public utilities that are located off-site with which connection is planned or located within two hundred feet of the site boundaries.
- 11** Soil types and approximate soil boundaries based on U.S. Department of Agriculture Natural Resources Conservation Service (formerly U.S. Soil Conservation Service) data.
- 12** Copies of existing covenants, easements and/or rights-of-way on the property.
- 13** The location of all building setbacks required by the Zoning Ordinance by use of dashed lines and labeled "Minimum Building Setback Lines" and the location of setbacks from Raymond's protected shorelands as described in Article III, Section 3.320 (02) of the Raymond Zoning Ordinance.
- 14** The location of aquifer boundaries and well head protection areas.
- 15** Any known hazardous issues prior to the submission of the applicant's application to the planning

board.

- 16 NH Department of Environmental Services septic system application.
- 17 NH Wetlands Board "Alteration of Wetlands" application.
- 18 NH "Alteration of Terrain" application.
- 19 Town of Raymond Driveway Access application or the NH Department of Transportation Driveway Access application.
- 20 NH Water Supply & Pollution control commission WS 411 applications for underground storage tanks, as regulated by RSA 146-C.
- 21 Army Corps of Engineers application, if applicable.
- 22 Any other State or Federal applications, if applicable.
- 23 All Zone G Land shall be calculated and shown on the plans.

5.03 SITE PLAN AND INFORMATION

The following information shall be provided on the submitted plan for approval:

- 01 On a scale of 1" = 20' up to 1" = 50', proposed grades, drainage systems, structures and topographic contours at intervals not exceeding two feet with spot elevations where slope is less than 2%. All proposed or new topographic contours are to be represented with bold unbroken lines with contour number in block.
- 02 The shape, size, height and location of the proposed structures, including expansion of existing buildings.
- 03 Proposed streets, driveways, parking spaces and sidewalks with indication of direction of travel for streets and drives, and inside radii of all curves. The width of streets, driveways and sidewalks, as well as the total number of parking spaces, and points for future right-of-way and/or street access to abutting parcels to accommodate the continuation of future development.
- 04 Loading spaces and facilities associated with the structures on the site.
- 05 The size and location of all proposed public and private utilities.
- 06 The location, type and size of all proposed landscaping and screening. Identification of a buffer zone of dense planting where the site abuts a zoning boundary.
- 07 Exterior lighting plan showing ground-level dispersing and lighting intensity in accordance with the Town of Raymond Outdoor Lighting Design Standards, as may be amended from time to time.
- 08 Proposed signs to be located on the site.

- 09** A stormwater management plan designed and stamped by a New Hampshire registered Professional Engineer including plans for retention and slow release of storm water where necessary.
- 10** Plans for snow removal and storage.
- 11** Surface treatment proposed for all disturbed areas.
- 12** A legend identifying and clarifying all drafting and designation symbols.
- 13** A Traffic Impact Analysis shall be prepared by a New Hampshire registered Professional Engineer including any traffic control devices necessary in conjunction with the site plan. Increases and decreases in traffic volume and patterns generated by the development onto Town or State roads and sight distances at the point of access onto a Town Road shall be shown. The level of the impact study is dependent upon the proposed intensity of the use.
- 14** Construction plans shall be prepared for all required improvements. Plan sheets shall be of the same size as the site plan. The following information shall be shown:
 - a. Plans and construction details of all areas to be disturbed for construction of streets, drives, parking lots, sidewalks, drainage structures, sewers, water and electric lines, erosion and sediment control structures and other areas to be disturbed for the construction of the improvements.
 - b. Profiles of all proposed streets, driveways, sewers and drainage structures. Profiles shall show existing and proposed elevations along the center lines of all proposed improvements. Profile scale shall be one-inch equals forty feet horizontal scale, and one-inch equals four feet vertical scale.
 - c. Cross sections of all proposed streets and driveways at one hundred-foot stations and at all catch-basins or culverts. Cross sections shall show all existing grades, proposed subgrades, proposed final grades and all utilities and other structures. Cross sections shall be drawn at a scale of not more than one-inch equals ten feet vertically, and one-inch equals fifty feet horizontally. Cross sections shall be provided at regular intervals throughout the site.
 - d. Erosion and sediment control plans and other information indicating how increased runoff, sedimentation and erosion shall be controlled during and after construction of required improvements.
 - e. Landscaping Plan for the entire site including proposed species (number, spacing, size, planting details-list native species per NHDES); proposed decorative features; buffers and screening devices and any other information that can reasonably be required for an informed decision to be made by the Planning Board.
 - f. Architectural Concept Drawings shall be submitted in triplicate; one copy each for the Board, the Code Enforcement Officer and the Fire Department, for all proposed buildings or building expansions. Said plans shall consist of plan and exterior elevation

views or proposed improvements, with external mechanical components of the building (i.e. heating, ventilation and air conditioning). Plans shall be conceptual only, but of sufficient detail to determine compliance with Town Regulations.

- 15 Open spaces, green areas, public or common land, Raymond protected shoreland and setback lines.

5.04 OTHER ITEMS REQUIRED by the Planning Board, AS APPLICABLE

- 01 Location and results of test pits, location of primary and secondary leach bed sites.
- 02 NH Department of Environmental Services septic system design approval
- 03 NH Wetlands Board "Alteration of Wetlands" Permit.
- 04 Town of Raymond Driveway Access Permit.
- 05 NH Department of Transportation Driveway Access Permit.
- 06 Traffic Impact Analysis.
- 07 Soil Erosion and Sediment Control Plan, in accordance with the Raymond Stormwater Management Regulations, as may be amended from time to time.
- 08 NH Water Supply & Pollution control commission WS 411 Permit for underground storage tanks, as regulated by RSA 146-C.
- 09 High Intensity Soil Mapping.
- 10 Army Corps of Engineers Permit, if applicable.
- 11 Any other State or Federal permits as identified.
- 12 Community Impact Analysis

5.05 GROUNDWATER PROTECTION

The quality of groundwater as defined by RSA 485-C: 2 VIII. shall not be adversely affected by the proposed development. The applicant shall certify that the proposed development does not violate the rules and regulations of Chapter 485-C, Groundwater Protection Act, regarding groundwater and shall meet the following requirements. Proposed development located within the Town of Raymond's existing Zone I – Groundwater Conservation District shall certify zoning compliance to the Planning Board as part of the site plan review approval process.

- 01** Any application for site plan review which involves the proposed receiving, handling, storing or processing of any regulated substance (as defined by RSA 339-A:2) shall disclose this information as part of the application submission. List of all appropriate state permits, as required by the New Hampshire Department of Environmental Services (NHDES) for the proposed use shall be submitted as part of the site plan application.
- 02** Site plan applications which involve property contaminated by hazardous or toxic materials (as defined by RSA 339-A: 2) shall disclose such information as part of the application. If the Planning Board finds that a potential health risk or an environmental threat exists from a previous use or existing use of the site, then the Planning Board shall require that any environmental assessment that has been completed and submitted to NHDES shall be submitted to a third-party qualified review professional of the Planning Board's choice, at the applicant's expense, prior to any Planning Board action.
- 03** All site plans submitted to the Planning Board for review shall identify:
 - a. All existing aquifers as documented by the Town of Raymond's Aquifer Transmissivity Map (copies available in the Planning and Development Department and as aquifer transmissivity GIS data available on NHGRANIT);
 - b. All designated wellhead protection areas for public water systems, as documented in the *Combined Aquifer, Surficial Geology and Wellhead Protection Areas Map*, as may be amended from time to time, and on NHDES websites and databases, as may be amended from time to time;
 - c. The location of all known and potential contamination sources, as documented on NHDES websites and databases; (prior to the complete application submission to the Planning Board)
 - d. A map of natural resources on and near the site;
 - e. A listing of the types and quantities of regulated and hazardous substances and pollutants which may be used on the site;
 - f. A map and/or diagram of facilities on the site related to groundwater protection, including secondary containment structures, loading/unloading areas, drinking water wells, septic systems, underground storage tanks and storm drain inlets, as applicable:
 - i. A listing of all state and federal regulatory requirements for the proposed use and a note on the plan which identifies the specific rules related to groundwater protection, as applicable to regulated substances (Env-Wq. 402)², groundwater discharge (Env-Wq. 402) and storm water management (e.g. Env-Wq. 1500, AoT);

- ii. Identification and provision for adequate security of all groundwater protection Best Management Practices (BMPs) proposed for the use;
- iii. Identification of any restrictions against discharges to groundwater, including direct and indirect discharges, as required by state and federal permits and approvals;
- v. Verification or approval that all general-purpose floor drains be connected to an onsite holding tank or a system authorized through a state subsurface disposal permit;
- vi. Verification or approval that the design of all storm water management and drainage facilities and structures shall not increase flooding or the potential for pollution of surface or groundwater, on-site and off-site; and
 - a. Submittal of an adequate Spill Prevention, Control and Countermeasure (SPCC) Plan in accordance with Article IV, Section 4.244 of the Raymond Zoning Ordinance and approved by the Technical Review Committee, particularly the Fire Chief and Emergency Management Director.

² Env-Wq. signifies that this is a Water Quality/Quantity rule as published by the New Hampshire Department of Environmental Services. See <http://des.nh.gov/organization/commissioner/legal/rules/index.htm#waterq>

ARTICLE VI – REVIEW STANDARDS

In considering applications for site plan approval, the Planning Board shall be guided by the standards herein after set forth. Such standards shall be considered minimum standards and be modified by the Board, when in its opinion, specific circumstances surrounding the site suggest a modification; with such modification not adversely affecting the purpose and intent of the Site Plan Review Regulations.

6.01 ACCESS DESIGN

- 01** Traffic access to the site from any street or highway shall ensure the safety of vehicles and pedestrians.
- 02** The Planning Board shall approve the design for a proposed access/egress point onto the public way, which point shall provide an adequate sight distance, grade, width and curb or with State Highway Access Permit.
- 03** In all cases, the number of points of access to a given street shall be held to a minimum, preferably one, in order to reduce traffic hazards from turning movements and to lessen the installation of traffic control devices, when possible.
- 04** The Board may require improvement of existing access/egress point(s) to provide a safe flow onto abutting streets or highways, should increase traffic be generated onto them by the development.
- 05** Off-site improvements, including but not limited to increasing right-of-way width;

acceleration/deceleration lanes; curbing; signal devices; water, wastewater or drainage extensions; street lighting; sidewalks; additional landscaping; and emergency traffic control devices (i.e. opticoms); may be required.

- 06** Traffic circulations, pedestrian access, parking and loading facilities, and emergency and fire access shall be designed and located to ensure safety on the site. It is the policy of the Planning Board to require interconnectivity of adjacent or abutting parcels and parking areas.
- 07** The Planning Board shall review the proposed development to assure that all necessary permits have been received from governmental agencies from which approvals are required by Federal or State law, including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 U.S.C. 1334.
- 08** The Planning Board shall require that all proposals include Base Flood Elevation (BFE) data within such proposals (i.e. floodplain boundary (50-year flood elevation and 100-year flood plain))
- 09** Provisions shall be made to assure that all proposals for development are consistent with the need to minimize flood damage, and that all public utilities and facilities such as wastewater, electrical and water systems are constructed, and that adequate drainage is provided so as to reduce exposure to flood hazards. Design provisions shall also be made to minimize or eliminate infiltration of floodwaters into new or replacement water supply systems and/or sanitary sewage systems, and discharges from the systems into floodwaters. On-site waste disposal systems shall be located so as to avoid their impairment or contamination resulting from them during flooding.

6.02 STREET CONSTRUCTION STANDARDS

- 01** Streets, drives and access ways in non-residential and multi-family developments shall be constructed to Town specifications as set forth in the Town of Raymond Subdivision Regulations and the Raymond Road Construction Standards, with the following exceptions:
 - a. The paved travel way shall be a minimum of twenty-five feet wide.
 - b. Bituminous asphalt paving shall be a minimum of four inches thick, applied in two compacted courses, consisting of a two- and one-half-inch binder and a one and one-half inch wearing course.
 - c. Cul-de-sacs shall have an interior landscaped green area with a minimum radius of fifty feet, paved width of twenty-five feet, and a radius to property line distance of ninety feet. All radii shall be calculated from the center line intersect of the roadway and cul-de-sac.

d. Roads design matrix

Statement of Intent: The intent of these design standards is to provide quality developments throughout the Town of Raymond which provide for effective transportation networks that will adequately serve ever-changing population densities as the community grows and the related capacity needs for multi-modal transportation types.

| Road Design Matrix Criteria | Public or Private Roads | | | |
|------------------------------------|-------------------------|----------------------|-------------|------------------|
| | Collector - Rural | Collector - Urban | Local Rural | Local Urban |
| Average Daily Traffic Volume (ADT) | 750 to 2,000 | 750 to 2,000 | <750 | <750 |
| Design Speed | 30 MPH | 25 MPH | 25 MPH | 25 MPH |
| Minimum ROW Width | 50' | 50' | 50' | 50' |
| Minimum Pavement Width | 25' | 25' | 24' | 24' |
| Minimum Shoulder Width each side | 4' | none (curbed) | 4' | none (curbed) |
| Minimum Horizontal Curve Radius | 250' | 200' | 200' | 200' |
| K-value / Crest | 30 | 20 | 20 | 20 |
| K-value / Sag | 35 | 30 | 30 | 30 |
| Minimum Tangent Length | 100' | 75' | 75' | 75' |
| Stopping Sight Distance | 200' | 155' | 155' | 155' |
| Curbing Requirement | No | Yes | No | Yes |
| Sidewalk Requirement | No | Yes | No | Yes |
| Closed Drainage Requirement | No | Yes | No | Yes |

Information for 25MPH/20MPH was gathered from AASHTO "A Policy on Geometric Design of Highways and Streets" 2011 6th Edition

Minimum Horizontal Curve Radius from Table 3-13b (Minimum Radii for Low-Speed Urban Streets)

K-value/Crest, K-value/Sag & Stopping Sight Distance from Tables 3-34 and 3-36 (Design Controls for Crest and Sag Vertical Curves)

For Rural Collectors, use AASHTO Green Book

For Urban Collectors, use *Designing Walkable Urban Thoroughfares -- A Context Sensitive Approach*

* Any waiver request must meet minimum AASHTO standards

6.03 TRAFFIC IMPACT ANALYSIS

The review of any site plan conducted by the Board under these Regulations shall ascertain that adequate provisions have been made by the owner or his/her authorized agent for traffic safety. To facilitate this review, the Board shall require the developer to submit a traffic impact analysis, when deemed necessary, due to the size, location or traffic generating characteristic of the development.

6.04 CONSTRUCTION SITE STORMWATER RUNOFF CONTROL: EROSION AND SEDIMENT CONTROL

01 Introduction and Purpose

During the construction process, soil is highly vulnerable to erosion by wind and water. Eroded soil endangers water resources by reducing water quality and causing the siltation of aquatic habitat for fish and other desirable species. Eroded soil can also cause damage to adjacent properties and impair the function of municipal drainage systems and infrastructure. In addition, clearing and grading during construction cause the loss of native vegetation that support terrestrial and aquatic habitats.

The purpose of this regulation is to safeguard persons, protect property, and prevent damage to infrastructure and the environment in Town of Raymond. This regulation will also promote the public welfare by guiding, regulating, and controlling the design, construction, use, and maintenance of any development or other activity that disturbs or breaks the topsoil or results in the movement of earth on land in Town of Raymond.

02 Definitions

Clearing: Any activity that removes the vegetative surface cover.

Drainage Way: Any channel that conveys surface runoff throughout the site.

Erosion Control: A measure that prevents erosion.

Erosion and Sediment Control Plan: A set of plans prepared by or under the direction of a licensed professional engineer indicating the specific measures and sequencing to be used to control sediment and erosion on a development site during and after construction.

Grading: Excavation or fill of material, including the resulting conditions thereof.

Perimeter Control: A barrier that prevents sediment from leaving a site by filtering sediment-laden runoff or diverting it to a sediment trap or basin.

Phasing: Clearing a parcel of land in distinct phases (with limits of clear-cutting site to 5 acres per phase), with the stabilization of each phase completed before the clearing of the next.

Sediment Control: Measures that prevent eroded sediment from leaving the site.

Site: A parcel of land or a contiguous combination thereof, where grading work is performed as a single unified operation.

Site Development Permit: A permit issued by the municipality for the construction or alteration of ground, and improvements and structures for the control of erosion, runoff, and grading.

Stabilization: The use of practices that prevent exposed and stockpiled soil from eroding, slumping or failure.

Start of Construction: The first land-disturbing activity associated with a development, including land preparation such as clearing, grading, and filling; installation of streets and walkways; excavation for basements, footings, piers, or foundations; erection of temporary forms; and installation of accessory buildings such as garages.

Watercourse: Any body of water, including, but not limited to lakes, ponds, rivers, streams, and bodies of water delineated by Town of Raymond.

Waterway: A channel that directs surface runoff to a watercourse or to the public storm drain.

03 Site Plan Review Approval

- a. A site plan application proposing land-disturbing activity of 3,000 or more square feet requires the approval of an Erosion and Sediment Control Plan.
- b. No site plan approval is required for the following activities:
 - 1) Any emergency activity that is immediately necessary for the protection of life, property, or natural resources.
 - 2) Existing nursery and agricultural operations conducted as a permitted main or accessory use.
- c. Each application shall bear the name(s) and address(es) of the owner or developer of the site, and of any consulting firm retained by the applicant together with the name of the applicant's principal contact at such firm and shall be accompanied by a filing fee.
- d. Each application shall include a statement that any land clearing, construction, or development involving the movement of earth shall be in accordance with the Erosion and Sediment Control Plan and that an engineer or construction site manager shall be on site on all days when construction or grading activity takes place.
- e. The applicant will be required to file performance guarantee, letter of credit, or other improvement security in an amount deemed sufficient by the Planning Board to cover all costs of improvements, landscaping, maintenance of improvements for such period as specified by the Planning Board, and engineering and inspection costs to cover the cost of failure or repair of improvements installed on the site. If a performance guarantee is required for overall general site construction, sediment and erosion control measures shall be included in the construction cost estimate for the performance guarantee.

04 Erosion and Sediment Control Plan

- a. The Erosion and Sediment Control Plan shall include the following:
 - 1) A natural resources map identifying soils, forest cover, and resources protected under other chapters of this code. Note: This map should be at a scale no smaller than (1" =50")
 - 2) A sequence of construction of the development site, including stripping and clearing; rough grading; construction of utilities, infrastructure, and buildings; and final grading and landscaping. Sequencing shall identify the expected date on which clearing will begin, the estimated duration of exposure of cleared areas, areas of clearing, installation of temporary erosion and sediment control measures, and establishment of permanent vegetation.
 - 3) All erosion and sediment control measures necessary to meet the objectives of this local regulation throughout all phases of construction and after completion of development of the site. Depending upon the complexity of the project, the drafting of intermediate plans may be required at the close of each season.

- 4) Seeding mixtures and rates, types of sod, method of seedbed preparation, expected seeding dates, type and rate of lime and fertilizer application, and kind and quantity of mulching for both temporary and permanent vegetative control measures. As approved by the Planning Board.
 - 5) Provisions for maintenance of control facilities, including easements and estimates of the cost of maintenance.
- b. Modifications to the plan shall be processed and approved or disapproved in the same manner as Section IV of this regulation, may be authorized by (*erosion and sediment control agency*) by written authorization to the permittee, and shall include
- 1) Major amendments of the erosion and sediment control plan submitted to the Planning Board for review and approval.
 - 2) Field modifications of a minor nature do not require Planning Board approval but should be noted on the final As-Built Plans.

05 Site Design Requirements

- a. Grading, erosion control practices, sediment control practices, and waterway crossings shall meet the design criteria set forth in the most recent version of (*erosion and sediment control manual*) and shall be adequate to prevent transportation of sediment from the site to the satisfaction of (*erosion and sediment control agency*). Cut and fill slopes shall be *no greater than 2:1*, except as approved by (*erosion and sediment control agency*) to meet other community or environmental objectives.
- b. Clearing and grading of natural resources, such as forests and wetlands, shall not be permitted, except when in compliance with all other chapters of this Code. Clearing techniques that retain natural vegetation and drainage patterns, as described in the NH Stormwater Manual: Volume 3 Erosion and Sediment Controls During Construction (December 2008 as revised), shall be utilized.
- c. Clearing, except that necessary to establish sediment control devices, shall not begin until all sediment control devices have been installed and have been stabilized.
- d. Phasing shall be required on all sites disturbing greater than 5 acres, with the size of each phase to be established at plan review and as approved by the Planning Board.
- e. Erosion control requirements shall include the following:
 - 1) Erosion control measures shall be installed prior to the commencement of land disturbance activities. At the conclusion of such activities, soil stabilization shall be completed within 5 days.
 - 2) If seeding or another vegetative erosion control method is used, it shall become established within two weeks or may require the site to be reseeded or a nonvegetative option employed.
 - 3) Special techniques that meet the design criteria outlined in (*erosion and sediment control manual*) on steep slopes or in drainage ways shall be used to ensure stabilization.
 - 4) Soil stockpiles must be stabilized or covered at the end of each workday and maintained at no greater than 1:1 slope.
 - 5) The entire site must be stabilized, using a heavy mulch layer or another method that does not require germination to control erosion, at the close of the construction season.
 - 6) Techniques shall be employed to prevent the blowing of dust or sediment from the site.
 - 7) Techniques that divert upland runoff past disturbed slopes shall be employed.
- F) Sediment controls requirements shall include
 - 1) Settling basins, sediment traps, or tanks and perimeter controls.

- 2) Settling basins that are designed in a manner that allows adaptation to provide long term stormwater management, if required.
 - 3) Protection for adjacent properties using a vegetated buffer strip in combination with perimeter controls
- G) Waterway, watercourse and wetland protection requirements shall include when applicable:
- 1) A temporary stream and/or wetland crossing installed and approved by the NH Department of Environmental Services (NHDES) if a wet watercourse or wetland will be crossed regularly during construction;
 - 2) Stabilization of the watercourse channel and/or wetland before, during, and after any in-channel work per NHDES requirements;
 - 3) On-site stormwater conveyance channels designed according to NHDES requirements; and
 - 4) Stabilization adequate to prevent erosion located at the outlets of all pipes and paved channels.
- H) Construction site access requirements shall include:
- 1) a temporary access road provided at all sites; and
 - 2) other measures required by the Planning Board in order to ensure that sediment is not tracked onto public streets by construction vehicles or washed into storm drains
- I) Waste Removal and Disposal
- 1) All waste generated on the site shall be controlled and discarded properly including building materials, concrete and concrete wash our effluent, chemicals, litter and sanitary wastes.
 - 2) Waste shall not be discharged to the municipal MS4 system.

06 Site Inspection

- a. The Planning Board or its designated agent shall make inspections as hereinafter required and either shall approve that portion of the work completed or shall notify the permittee wherein the work fails to comply with the Erosion and Sediment Control Plan as approved. Plans for grading, stripping, excavating, and filling work approved by the Planning Board shall be maintained at the site during the progress of the work. To obtain inspections, the permittee shall notify the town engineer at least two working days before the following:
 - 1) Start of construction
 - 2) Installation of sediment and erosion measures
 - 3) Completion of site clearing
 - 4) Completion of rough grading
 - 5) Completion of final grading
 - 6) Close of the construction season
 - 7) Completion of final landscaping
- b. The permittee or their agent shall make regular inspections of all control measures in accordance with the inspection schedule outlined on the approved Erosion and Sediment Control Plan(s). The purpose of such inspections will be to determine the overall effectiveness of the control plan and the need for additional control measures. All inspections shall be documented in written form and submitted to the Planning Board at the time interval specified in the site plan approval decision.
- c. The Planning Board or its designated agent shall enter the property of the applicant as deemed necessary to make regular inspections to ensure the validity of the reports filed under Section b.

07 Separability

The provisions and sections of this ordinance shall be deemed to be separable, and the invalidity of any portion of this ordinance shall not affect the validity of the remainder.

6.05 UTILITIES

- 01 A layout indicating how the site will be served by electric, telephone and any other public utilities shall be provided. If a utility company requires an easement to provide service, no final approval shall be granted by the Board until such easement(s) are secured. If no easement(s) are required, a letter of intent to provide service from the utility company/companies must accompany the application. All utilities shall be located underground. Where practical, adequate separation between underground electric, telephone and cable utilities, and all other underground utilities, such as water and drainage, shall be maintained, and in instances where water, drains or sewers are installed in a common trench with electric, telephone or cable.
- 02 In areas of the Town where municipal water is not provided, water supply systems must be sized to meet the needs of the proposed use. Should connection to the municipal water system be requested, the applicant shall obtain a letter from the Raymond Water Department indicating acceptance of the proposed design and agreement to furnish the requested service(s). If the capacity of the system is such that the Raymond Water Department denies application until such time as (1) the Town, based upon its Capital Improvement Program, is able to upgrade the facilities and provide service, or (2) a proposal is agreed upon to upgrade said service at the Petitioner's expense. If the proposed location for a project under review by planning board is near the town water system, the project shall connect to the town water system. **Distance is needed at next PB work Session**
- 03 The expansion of existing uses which creates additional demand for water or sewage facilities shall be subject to this section. Any extension of the municipal facilities shall be at the applicant's expense.

6.06 PARKING STANDARDS

For the safety of the public, every site considered under this Regulation shall have off-street parking only. No parking shall be permitted on public rights-of-way, nor will parking be permitted where it will obstruct vehicle access to a property or to a public right-of-way. Access to the parking site shall be from on-site travel ways. Vehicle access shall not be considered part of the parking lot area.

- 01 The Planning Board recognizes that the following Parking Requirements Chart cannot cover every circumstance that may arise. The Board is authorized to use the following parking requirements as a minimal guide for uses not identified in the Chart.

PARKING REQUIREMENTS CHART

- ◆ **Auto/Truck - Sales Only**
 - Minimum 5 spaces; plus
 - 1 space per every 10 vehicles
- ◆ **Auto/Small Truck Service**
 - 1 space per every 200 SF of gross area; plus
 - 1 space per service bay
- ◆ **Bank**
 - 12 spaces per every 1,000 SF of gross area
- ◆ **Emergency Services**
 - 1 space per every 200 SF of gross floor area
- ◆ **Gasoline Supplier**
 - 5 spaces minimum; plus
 - 1 space per pump; plus
 - 2 spaces per service bay
- ◆ **Hotels/Motels**
 - 1.5 spaces per unit
- ◆ **Industrial - Light**
 - 1 space per every 2 employees; or
 - 1 space per every 200 SF of gross area
- ◆ **Industrial - Heavy**
 - 1 space for every 2 employees; plus
 - 1 space for every 2,000 SF of gross area
- ◆ **Institutional – Elementary & Middle School**
 - 5 spaces per classroom
- ◆ **Institutional – High School**
 - Spaces equal to ½ of total school capacity
- ◆ **Institutional – Hospital/Clinic**
 - 2 spaces per bed; or
 - 1 space per every 150 SF of gross area, whichever is greater
- ◆ **Institutional – Nursing Home**
 - 3 spaces per every 5 beds
- ◆ **Child or Adult Care Facilities**
 - 2 spaces per employee
- ◆ **Institutional – Special School/Church**
 - 1 space per every 100 SF of gross area
- ◆ **Institutional - Stadium**
 - 1 space per every 4 seats
- ◆ **Institutional - Theater**
 - 1 space per every 3 seats
- ◆ **Library**
 - 1 space per every 33 SF of gross floor area
- ◆ **Office – Low Volume (i.e. Construction; Funeral Home)**
 - 3 spaces per every 1,000 SF of gross area
- ◆ **Office – High Volume (i.e. Health Aid Services; Attorneys; Insurance; Real Estate; Government Offices)**
 - 6 spaces per every 1,000 SF of gross area
- ◆ **Recreational Facilities – Bowling Alley; Skating Rink; Indoor Tennis Court; Exercise Facility; Privately Owned Golf Course**
 - 1 space per every 3 people the facility is designed to handle at maximum capacity; plus
 - 1 space per every 200 SF of gross building area
- ◆ **Recreational Facilities – Golf Driving Range; Miniature Golf**
 - 1 space per tee; plus
 - 1 space per every 200 SF of gross area
- ◆ **Residential/multi-family**
 - 3 spaces per unit

- ◆ **Restaurants - Sit-Down; Family; Carry-Out; Drive-In**
 - 1 space per every 2 seats; plus
 - 1 space per every 200 SF of gross area
- ◆ **Retail – Low Volume (i.e. Construction & Remodeling Services)**
 - 2.5 spaces per every 1,000 SF of gross area
- ◆ **Retail – Medium Volume (i.e. Clothing; Shoes; Laundromat/Dry Cleaning; Home Furnishing; Video Store; Hardware; Beauty Parlor; Pet Shop)**
 - 5 spaces per every 1,000 SF of gross area
- ◆ **Retail – High Volume (i.e. Convenience Store; Pharmacy; Grocery; Ice Cream Stand)**
 - 8 spaces per every 1,000 SF of gross area
- ◆ **Truck Service**
 - 1 space per 200 SF of gross area; plus
 - 1 space per service bay; plus
 - Space for oversized trucks

02 Handicapped parking is required and shall conform to the most current State and Federal law in place at the time of application.

03 The Planning Board has the prerogative to adjust these requirements to particular circumstances. This decision will be based on the expected number of trips generated by the activity at its peak hour. When there is mixed or joint use, combination of individual use demands on parking will be considered.

04 Parking spaces shall conform to the following:

- a. Parking spaces shall not be used for permanent storage, nor will they be considered loading areas. No activities will be permitted except those for which the spaces were intended.
- b. All parking areas shall be set back no closer than ten feet from any street or lot line and must be delineated on the ground. Landscaping within the setback to the external lot line shall be encouraged whenever possible. All parking areas shall be bordered by a curb or a substantial bumper of masonry, concrete, or bituminous concrete.
- c. A corresponding increase in parking spaces based on the use/activity shall accompany any extension or expansion of the physical plant.
- d. Each required off-street parking space shall be at least nine feet in width, measured perpendicular to the sideline; and at least twenty feet in length, measured parallel to the sideline along the center of the space. For parallel parking, the length of the parking space shall be increased to twenty-two feet. Handicapped spaces shall be at least twelve feet wide and twenty feet in length. Each off-street parking space shall open directly upon aisle or drive width as follows:

| <u>Parking Angle</u> | <u>Aisle Width</u> |
|----------------------|--------------------|
| 45 degrees | 20 feet |
| 60 degrees | 20 feet |
| 90 degrees | 20 feet |

- e. The aisle of drives shall be unobstructed and allow for the passage of emergency vehicles at all times. The angle shall be measured between the center line of the parking space and the center line of the aisle.
- f. All off-street parking, loading or unloading shall be suitably improved, graded, paved and maintained so as to cause no nuisance from dust or storm drainage including ice and snow removal. Provisions shall be made more snow removal so as to ensure that no snow will be pushed, shoveled or placed in a public way.
- g. Adequate snow storage areas shall be provided on site.
- h. Redevelopment or development within highly congested areas may require submission of alternate parking arrangements.
- i. In instances where a waiver is requested for relief from the number of parking spaces required by the Raymond Site Plan Review Regulations for a project, an applicant must present a plan showing the ability to install the full number of spaces in the future, if the need arises.

6.07 PARKING AREAS AND ACCESS DRIVES

Drives and parking areas shall be constructed per the Town of Raymond Subdivision Regulations for Design of Streets and Roads, and in accordance with the following specifications:

- 01** Loam and/or unstable material shall be removed to a solid base material.
- 02** A bank run gravel sub-base of twelve inches shall be applied and compacted, followed by a six-inch base of crushed gravel, then compacted and rolled true to grade lines. Said compacting shall be to 95% of the sub-grade materials' modified proctor value.
- 03** A two- and one-half-inch binder course, and a one and one-half inch wearing course of bituminous concrete pavement shall be installed.
- 04** The minimum grade for parking areas shall be 0.5%. The maximum grade shall be 5%.
- 05** All construction materials and methods shall be in accordance with the State of New Hampshire Department of Transportation, Standard Specifications for Road and Bridge Construction, latest edition.

6.08 LOADING SPACE STANDARDS

- 01** No on-street loading or unloading shall be permitted, unless specifically approved by the Planning Board.
- 02** Loading docks or loading areas shall not be permitted within fifty feet of an abutting property line with a different zoning classification and shall be confined to the side or rear of a building. Any loading dock facing an abutting property line shall be screened as effectively as is practical, through the combination of fencing material and natural vegetation or terrain. Such

screening shall be subject to the approval of the Planning Board.

- 03** The actual size and construction of loading spaces shall be determined by its proposed use and approved by the Planning Board as such. Each area shall be designed so that backing or maneuvering can be accomplished in such a way that trucks will enter and leave the lot driving forward.
- 04** The loading area shall be surfaced with the same material used in the parking areas, with the exception of landing areas, which shall be concrete. The loading area shall also be subject to the same drainage requirements. A loading area plan shall accompany the final Site Plan.

6.09 FIRE PROTECTION

- 01** The applicant shall meet with the Fire Department to review the proposed protection activities, such as fire alarms, sprinkler systems, fire hydrants, dry hydrants, emergency access and cisterns that shall be shown on the site plan.
- 02** Dry hydrants and/or cisterns shall be required if Municipal Water is not located within one-half mile of the entrance to the proposed development.
- 03** A dry hydrant and/or cistern shall be considered adequate if it is capable of providing thirty thousand gallons of water at all times and under all conditions (based on one thousand gpm for thirty minutes) and is protected by a suitable chain link fence surrounding the entire pond perimeter. Cisterns need not be fenced.
 - a. The Raymond Fire Chief shall be the sole authority on adequacy of dry hydrants or cisterns.
 - b. The applicant shall be responsible for providing hydrant standpipe fill connections in accordance with Raymond Fire Department Regulations.
 - c. Dry hydrants, cisterns, and the land upon which they are cited, shall be the responsibility of the Homeowners Association or owner for care and maintenance.
 - d. Cisterns shall be constructed in accordance with Raymond Fire Department Regulations and good engineering practice.
- 04** The Fire Chief shall require a key box for any and all of the following:
 - a. Non-residential construction;
 - b. Multi-family construction;
 - c. Industrial construction;
 - d. Any property protected by an automatic alarm system;

- e. Anywhere access to or within a structure or an area on the property is unduly difficult due to secured openings;
- f. Anywhere immediate access is necessary for lifesaving and firefighting purposes.

Note: The key box shall be of a type approved by the Fire Chief and is to be installed in an approved location. Key box installations shall be in accordance with Raymond Fire Department installation for same.

- 05** The manufacturing, utilization and storage of pyrophoric or explosive materials shall be in strict accordance with the safety codes and standards of the National Fire Protection Association.

6.10 LANDSCAPING AND SCREENING

- 01** Installation, preservation and maintenance of landscaping and preservation of natural and scenic features shall be of prime importance and shall be undertaken by the applicant to enhance the environment of the development and of the Town of Raymond. As approved by the Planning Board.
- 02** In order to visually obscure certain uses or portions of specific uses, which by their nature are unsightly, or which by their scale or design present a potentially negative impact to adjacent properties, the developer shall provide screening in the form of a fence, wall, hedge, landscaping, earth berm, natural buffer area, or a combination thereof. The following uses shall be screened from adjacent properties and public view from a public street:
 - a. Dumpster/trash handling areas;
 - b. Waste disposal receptacles;
 - c. Service entrances/utility facilities;
 - d. Loading docks;
 - e. Outdoor storage of material, equipment, motor vehicles or similar items.
- 03** Landscaping shall mean the permanent installation of hardy lawns, trees, shrubs and other plantings. Existing mature trees shall be retained and incorporated into the overall landscape plan, wherever practical. Materials such as bark mulch, chipping, crushed or fragmented stone, etc. may be used for accent purposes. However, such materials shall not be used for extensive cover of the ground. In the front yard area of any development, at least five percent (5%) of the area shall be landscaped. These landscaped areas shall contain trees at least one and one-half inches in caliper and shrubs one to three feet in height and continuous ground cover.

- 04 All planting areas intended to be mowed or maintained shall receive a minimum of four inches of compacted loam free of sod, clay and stones over one inch in diameter. Areas within and adjacent to parking lots and or developed areas that are not irrigated, six inches of loam is preferred. All organic material over two inches in diameter shall be raked out and removed. After placement of loam, planting areas shall be seeded with first quality lawn seed. Seed mixture shall be selected by a licensed landscape architect or an appropriate seed mixture based on soil type and application as established in the New Hampshire Stormwater Management Manual, Volume 3, as revised.
- 05 All landscape plans shall consist of a generous mix of ground cover treatments, evergreens, hardwood trees and ornamental growths. No one type of vegetation shall predominate.
- 06 Plans for meeting the screening and landscaping requirements shall be submitted by the developer as part of the site plan review approval process whenever a site plan is required. The Planning Board may require the applicant to engage the services of a licensed landscape architect to prepare any landscaping plan presented.
- 07 The owner and tenant of any property shall be jointly responsible for the maintenance of all required plant material and continued compliance with this section.

6.11 POST CONSTRUCTION STORMWATER MANAGEMENT STANDARDS

| Glossary of Acronyms | |
|-----------------------------|---|
| BMP | Best Management Practices |
| GIS | Geographic Information System |
| HSG | Hydrologic Soil Group |
| LID | Low Impact Development |
| MEP | Maximum Extent Practicable |
| MS4 | Municipal Separate Storm Sewer System |
| SMP | Stormwater Management Plan |
| SPCC | Spill Prevention, Control and Countermeasure Plan |

01 Purpose, Goals and Definitions

- 1. The purpose of post construction stormwater management standards is to provide reasonable guidance for the regulation of stormwater runoff to protect local natural resources from degradation and prevent adverse impacts to adjacent and downstream land, property, facilities, and infrastructure. These standards regulate discharges from stormwater and runoff from land development projects and other construction activities to control and minimize increases in stormwater runoff rates and volumes, soil erosion, stream channel erosion, and nonpoint source pollution associated with stormwater runoff.
- 2. The goal of these standards is to establish minimum stormwater management requirements and controls to protect and safeguard the general health, safety, and welfare of the public in the Town of Raymond. This regulation seeks to meet that goal through the following objectives:

- a. Minimize increases in stormwater runoff from any development to reduce flooding, siltation and streambank erosion and maintain the integrity of stream channels.
- b. Minimize increases in nonpoint source pollution caused by stormwater runoff from development which would otherwise degrade local water quality.
- c. Minimize the total volume of surface water runoff which flows from any specific site during and following development to not exceed the pre-development hydrologic condition to the maximum extent practicable as allowable by site conditions.
- d. Reduce stormwater runoff rates and volumes, soil erosion and nonpoint source pollution, wherever possible, through stormwater management controls and to ensure that these management controls are properly maintained and pose no threat to public safety or cause excessive municipal expenditures.
- e. Protect the quality of groundwater resources, surface water bodies and wetlands.

02 Minimum Thresholds for Applicability

- 1. The post-construction stormwater management standards apply to any development or redevelopment project which are subject to Site Plan Review and disturbs more than 10,000 square feet or disturbs more than 2,500 square feet within 100 feet of a surface waterbody.
- 2. For sites that disturb less than 10,000 square feet, the Planning Board may grant an exemption if the amount of the total site impervious cover created does not exceed 5,000 square feet. However, when an exemption is granted by the Planning Board, the following standards will still be applied to these projects as conditions of approval.
 - a. All runoff from new impervious surfaces and structures shall be directed to a subsurface filtration and/or infiltration device or properly discharged to a naturally occurring or fully replanted and vegetated area with slopes of 15 percent or less and with adequate controls to prevent soil erosion and concentrated flow.
 - b. Impervious surfaces for parking areas and roads shall be minimized to the extent possible (including minimum parking requirements for proposed uses).
 - c. All runoff generated from new impervious surfaces shall be retained on the development site and property.
 - d. Determination of compliance with standards (a.-c. above) will be made by the Planning Board on a case-by-case basis as site conditions and constraints will differ greatly between various development proposals.

3. The following activities are considered exempt from preparing and submitting a stormwater management plan:
 - a. Agricultural and forestry practices located outside wetlands and surface water setbacks and/or buffers.
 - b. Resurfacing and routine maintenance of existing roads and parking lots.
 - c. Exterior and interior alterations and maintenance to existing buildings and structures.

03 Stormwater Management for New Development

1. All proposed stormwater management practices and treatment systems shall meet the following performance standards:
 - a. Stormwater management and erosion and sediment control practices shall be located outside any specified buffer zones unless otherwise approved by the Planning Board. Alternatives to stream and wetland crossings that eliminate or minimize environmental impacts shall be considered whenever possible.
 - b. Low Impact Development (LID) site planning and design strategies are encouraged to be used to the maximum extent practicable (MEP) to reduce stormwater runoff volumes, protect water quality, and maintain predevelopment site hydrology. LID techniques have the goals of protecting water quality, maintaining predevelopment site hydrology. LID techniques that preserve existing vegetation, reduce the development footprint, minimize, or disconnect impervious area, and use enhanced stormwater best management practices (BMP's) (such as rain gardens, bio retention systems, tree box filters, and similar stormwater management landscaping techniques) shall be incorporated into landscaped areas. Capture and reuse of stormwater is strongly encouraged. The applicant must document in writing why LID strategies are not appropriate when not used to manage stormwater.
 - c. All stormwater treatment areas shall be planted with native plantings appropriate for the site conditions: trees, grasses, shrubs and/or other native plants in sufficient numbers and density to prevent soil erosion and to achieve the water quality treatment requirements of this section.
 - d. All stormwater installations and areas that receive rainfall runoff must be designed to drain within a maximum of 72 hours for vector control.
 - e. Salt storage areas shall be fully covered with permanent or semi-permanent measures and loading/offloading areas shall be located and designed to not drain directly to receiving waters and maintained with good housekeeping measures in accordance with NH DES published guidance. Runoff from snow and salt storage areas shall enter treatment areas as specified above before being discharged to receiving waters or allowed to infiltrate into the groundwater. See NHDES published guidance fact sheets on road salt and water quality, and snow disposal at <http://des.nh.gov/organization/commissioner/pip/factsheets/wmb/index.htm>

- f. Surface runoff shall be directed into appropriate stormwater control measures designed for treatment and/or filtration to the MEP and/or captured and reused onsite.
- g. All newly generated stormwater from new development shall be treated on the development site. Runoff shall not be discharged from the development site to municipal drainage systems or privately owned drainage systems (whether enclosed or open drainage) or to surfacewater bodies and wetlands in rates greater than discharged under existing conditions (developed condition or undeveloped condition). A development plan shall include provisions to retain natural predevelopment watershed areas on the site by using the natural flow patterns.
- h. Runoff from impervious surfaces shall be treated to achieve at least 80% removal of Total Suspended Solids and at least 60% removal of both total nitrogen and total phosphorus using appropriate treatment measures, as specified in the NH Stormwater Manual. Volumes 1 and 2, December 2008, as amended (refer to Volume 2, page 6, Table 2.1 Summary of Design Criteria, Water Quality Volume for treatment criteria) or other equivalent means. Where practical, the use of natural, vegetated filtration and/or infiltration practices or subsurface gravel wetlands for water quality treatment is preferred given its relatively high nitrogen removal efficiency. All new impervious area draining to surface waters impaired by nitrogen, phosphorus or nutrients shall be treated with stormwater BMP's designed to optimize pollutant removal efficiencies based on design standards and performance data published by the UNH Stormwater Center and/or included in the latest version of the NH Stormwater Manual. Note: The Anti-Degradation provisions of the State Water Quality Standards require that runoff from new development shall not contribute additional pollutant loads to existing water body impairments.
- i. Measures shall be taken to control the post-development peak rate runoff so that it does not exceed pre-development runoff. Drainage analyses shall include calculations comparing pre- and post-development stormwater runoff rates (cubic feet/second) and volumes (cubic feet) for the 1-inch rainstorm and the 2-year, 10-year, 25-year, 50-year and 100-year 24-hour storm events. Similar measures shall be taken to control the post-development runoff volume to infiltrate the groundwater recharge volume GRV according to the following ratios of Hydrologic Soil Group (HSG) type versus infiltration rate multiplier: HSG-A: 0.4; HSG-B: 0.25; HSG-C: 0.1; HSG-D: 0.00. For sites where infiltration is limited or not practicable, the applicant must demonstrate that the project will not create or contribute to water quality impairment. Infiltration structures shall be in locations with the highest permeability on the site.

- j. The design of the stormwater drainage systems shall provide for the disposal of stormwater without flooding or functional impairment to streets, adjacent properties, downstream properties, soils, or vegetation.
 - k. The design of the stormwater management systems shall account for upstream and upgradient runoff that flows onto, over, or through the site to be developed or re-developed, and provide for this contribution of runoff.
 - l. Whenever practicable, native site vegetation shall be retained, protected, or supplemented. Any stripping of vegetation shall be done in a manner that minimizes soil erosion. development impervious surfaces, buildings and structures; surface water bodies and wetlands; drainage patterns, sub-catchment and watershed boundaries; building setbacks and buffers, locations of various hydrologic group soil types, mature vegetation, land topographic contours with minimum 2-foot intervals and spot grades where necessary for sites that are flat.
2. Submission Requirements for Stormwater Management Report and Plans
- a. The SMP shall include a narrative description and a Proposed Conditions Site Plan showing all post-development proposed impervious surfaces, buildings and structures; temporary and permanent stormwater management elements and BMP, including BMP GIS coordinates and GIS files; important hydrologic features created or preserved the site; drainage patterns, sub-catchment and watershed boundaries; building setbacks and buffers; proposed tree clearing and topographic contours with minimum 2-foot intervals. The plans shall provide calculations and identification of the total area of disturbance proposed on the site (and off site if applicable) and total area of new impervious surface created. A summary of the drainage analysis showing a comparison of the estimated peak flow and volumes for various design storms (see Table 1. Stormwater Infrastructure Design Criteria) at each of the outlet locations shall be included.
 - b. The SMP shall describe the general approach and strategies implemented, and the facts relied upon, to meet the goals of Section 1.15-3. A and C.: The SMP shall include design plans and/or graphical sketch(es) of all proposed above ground LID practices.
 - c. The SMP shall include calculations of the change in impervious area, pollution loading and removal volumes for each best management practice, and GIS files containing the coordinates of all stormwater infrastructure elements (e.g. catch basins, swales, detention/bioretention areas, piping).
 - d. The SMP shall include a description and a proposed Site Plan showing proposed erosion and sediment control measures, limits of disturbance, temporary and permanent soil stabilization measures in accordance with the NHDES Stormwater Manual Volume 3 (most recent version) as well as a construction site inspection plan including phased installation of best management practices and final inspection upon completion of construction.

- e. The SMP shall include a long-term stormwater management BMP inspection and maintenance plan (see Section 1.15-2. E) that describes the responsible parties and contact information for the qualified individuals who will perform future BMP inspections. The inspection frequency, maintenance and reporting protocols shall be included.
 - f. The SMP shall describe and identify locations of any proposed deicing chemical and/or snow storage areas. SMP will describe how deicing chemical use will be minimized or used most efficiently.
 - g. In urbanized areas that are subject to the EPA MS4 Stormwater Permit and will drain to chloride-impaired waters, any new developments and redevelopment projects shall submit a description of measures that will be used to minimize salt usage, and track and report amounts applied using the UNH Technology Transfer Center online tool (<http://www.roadsalt.unh.edu/Salt/>) in accordance with Appendix H of the NH MS4 Permit.
3. General Performance Criteria for Stormwater Management Plans
- a. All applications shall apply site design practices to reduce the generation of stormwater in the post-developed condition, reduce overall impervious surface coverage, seek opportunities to capture and reuse and minimize and discharge of stormwater to the municipal stormwater management system.
 - b. Water quality protection.
 - i. All stormwater runoff generated from new development or redevelopment shall not be discharged directly into a jurisdictional wetland or surface water body without adequate treatment.
 - ii. All developments shall provide adequate management of stormwater runoff and prevent discharge of stormwater runoff from creating or contributing to water quality impairment.
 - c. Onsite groundwater recharge rates shall be maintained by promoting infiltration through use of structural and non-structural methods. The annual recharge from the post development site shall maintain or exceed the annual recharge from pre-development site conditions. Capture and reuse of stormwater runoff is encouraged in instances where groundwater recharge is limited by site conditions All stormwater management practices shall be designed to convey stormwater to allow for maximum groundwater recharge. This shall include, but not be limited to:
 - i. Maximizing flow paths from collection points to outflow points.
 - ii. Use of multiple BMPs.
 - iii. Retention of and discharge to fully vegetated areas.
 - iv. Maximizing use of infiltration practices.
 - v. Stormwater System Design Performance Standards.

- d. Stormwater system design, performance standards and protection criteria shall be provided as prescribed in Table 1 below. Calculations shall include sizing of all structures and best management practices, including sizing of emergency overflow structures based on assessment of the 50-year and a 100-year 24- hour frequency storm discharge rate.
 - e. The sizing and design of stormwater management practices shall utilize new precipitation data from the Northeast Region Climate Center (NRCC) or the most recent precipitation atlas published by the National Oceanic and Atmospheric Administration (NOAA) for the sizing and design of all stormwater management practices. See the NRCC website at <http://precip.eas.cornell.edu/>.
 - f. All stormwater management practices involving bioretention and vegetative cover as a key functional component must have a landscaping plan detailing both the type and quantities of plants and vegetation to be in used in the practice and how and who will manage and maintain this vegetation. The use of native plantings appropriate for site conditions is strongly encouraged for these types of stormwater treatment areas. The landscaping plan must be prepared by a registered landscape architect, soil conservation district office, or another qualified professional.
4. Spill Prevention, Control and Countermeasure (SPCC) Plan. Any existing or otherwise permitted use or activity having regulated substances in amounts greater than five gallons, shall submit to the local official such as Fire Chief or Emergency Response Official a SPCC plan for review and approval. The Plan will include the following elements:
- a. Disclosure statements describing the types, quantities, and storage locations of all regulated substances that will be part of the proposed use or activity.
 - b. Owner and spill response manager’s contact information.
 - c. Location of all surface waters and drainage patterns.
 - d. A narrative describing the spill prevention practices to be employed when normally using regulated substances.
 - e. Containment controls, both structural and non-structural.
 - f. Spill reporting procedures, including a list of municipal personnel or agencies that will be contacted to assist in containing the spill, and the amount of a spill requiring outside assistance and response.
 - g. Name of a contractor available to assist in spill response, contaminant, and cleanup.
 - h. The list of available clean-up equipment with instructions available for use on-site and the names of employees with adequate training to implement containment and clean up response.

04 Stormwater Management for Redevelopment

1. Redevelopment (as applicable to this stormwater regulation) means:
 - a. Any construction, alteration, or improvement that disturbs existing impervious area (including demolition and removal of road/parking lot materials down to the erodible subbase) or expands existing impervious cover by any amount, where the existing land use is commercial, industrial, institutional, governmental, recreational, or multifamily residential.
 - b. Any redevelopment activity that results in improvements with no increase in impervious area shall be considered redevelopment activity under this regulation if capital cost of improvements is greater than 30% of the assessed property value.
 - c. Any new impervious area over portions of a site that are currently pervious.
2. The following activities are not considered redevelopment unless they meet the above criteria in section D.1.b.:
 - a. Interior and exterior building renovation.
 - b. Resurfacing of an existing paved surface (e.g. parking lot, walkway or roadway).
 - c. Pavement excavation and patching that is incidental to the primary project purpose, such as replacement of a collapsed storm drain.
 - d. Landscaping installation and maintenance.
3. Redevelopment applications shall comply with the requirements of Sections C.2 Submission Requirements for Stormwater Management Report and Plans, C.3 General Performance Criteria for Stormwater Management Plans, and C.4 Spill Prevention, Control and Countermeasure (SPCC) Plan.
4. For sites meeting the definition of a redevelopment project and having less than 60% existing impervious surface coverage, the stormwater management requirements will be the same as other new development projects. The applicant must satisfactorily demonstrate that impervious area is minimized, and LID practices have been implemented on-site to the MEP.
5. For sites meeting the definition of a redevelopment project and having more than 60% existing impervious surface area, stormwater shall be managed for water quality in accordance with one or more of the following techniques, listed in order of preference:
 - a. Implement measures onsite that result in disconnection or treatment of 100% of the additional proposed impervious surface area and at least 30% of the existing impervious area and pavement areas, preferably using filtration and/or infiltration practices.
 - b. If resulting in greater overall water quality improvement on the site, implement LID practices to the MEP to provide treatment of runoff generated from at least 60% of the entire developed site area.

6. Runoff from impervious surfaces shall be treated to achieve at least 80% removal of Total Suspended Solids and at least 60% removal of both total nitrogen and total phosphorus using appropriate treatment measures, as specified in the NH Stormwater Manual. Volumes 1 and 2, December 2008, as amended (refer to Volume 2, page 6, Table 2.1 Summary of Design Criteria, Water Quality Volume for treatment criteria) or other equivalent means. Where practical, the use of natural, vegetated filtration and/or infiltration practices or subsurface gravel wetlands for water quality treatment is preferred given its relatively high nitrogen removal efficiency. All new impervious area draining to surface waters impaired by nitrogen, phosphorus or nutrients shall be treated with stormwater BMP's designed to optimize pollutant removal efficiencies based on design standards and performance data published by the UNH Stormwater Center and/or included in the latest version of the NH Stormwater Manual. Note: The Anti-Degradation provisions of the State Water Quality Standards require that runoff from development shall not contribute additional pollutant loads to existing water body impairments.
7. All newly generated stormwater from redevelopment shall be treated on the development site. Runoff shall not be discharged from a redevelopment site to municipal drainage systems or privately owned drainage systems (whether enclosed or open drainage) or to surface water bodies and wetlands in rates greater than discharged under existing conditions (developed condition or undeveloped condition).
8. Off – site mitigation allowance: In cases where the applicant demonstrates, to the satisfaction of the Planning Board, that on-site treatment has been implemented to the MEP or is not feasible, off-site mitigation will be an acceptable alternative if implemented within the same sub watershed, within the project's drainage area or within the drainage area of the receiving water body. To comply with local watershed objectives the mitigation site would be preferably situated in the same sub watershed as the development and impact/benefit the same receiving water. Off-site mitigation shall only be approved by the Planning Board with the following conditions:
 - a. The Conservation Commission has been given the opportunity to advise the Planning Board regarding the proposed off-site mitigation.
 - b. The off-site mitigation shall be equivalent to no less than the total area of impervious cover NOT treated on-site. Treatment of the impervious area shall comply with all standards of this regulation.
 - c. An approved off-site location must be identified, the specific management measures identified, and if not owned by the applicant, with a written agreement with the property owner(s) and an implementation schedule developed in accordance with planning board review. The applicant must also demonstrate that there is no downstream drainage or flooding impacts that would result from not providing on-site management for large storm events.

05 Stormwater Management Plan and Site Inspections

1. The applicant shall provide that all stormwater management and treatment practices have an enforceable operations and maintenance plan and agreement to ensure the system functions as designed. This agreement will include all maintenance easements required to access and inspect the stormwater treatment practices, and to perform routine maintenance as necessary to ensure proper functioning of the stormwater system. The operations and maintenance plan shall specify the parties responsible for the proper maintenance of all stormwater treatment practices. The operations and maintenance shall be provided to the Planning Board as part of the application prior to issuance of any local permits for land disturbance and construction activities.
2. The applicant shall provide legally binding documents for filing with the Registry of Deeds which demonstrate that the obligation for maintenance of stormwater best management practices and infrastructure runs with the land and that the Town has legal access to inspect the property to ensure their proper function or maintain onsite stormwater infrastructure when necessary to address emergency situations or conditions.
3. The property owner shall bear responsibility for the installation, construction, inspection, and maintenance of all stormwater management and erosion control measures required by the provisions of these regulations and as approved by the Planning Board, including emergency repairs completed by the Town.

06 Stormwater Management Plan Recordation

1. Stormwater management and sediment and erosion control plans shall be incorporated as part of any approved site plan. A Notice of Decision acknowledging the Planning Board approval of these plans shall be recorded at the Registry of Deeds. The Notice of Decision shall be referenced to the property deed (title/book/page number) and apply to all persons that may acquire any property subject to the approved stormwater management and sediment control plans. The Notice of Decision shall reference the requirements for maintenance pursuant to the stormwater management and erosion and sediment control plans as approved by the Planning Board.
2. The applicant shall submit as-built drawings of the constructed stormwater management system following construction.

07 Inspection and Maintenance Responsibility

1. Select Board or their designated agent shall have site access to complete inspections to ensure compliance with the approved stormwater management and sediment and erosion control plans. Such inspections shall be performed at a time agreed upon with the landowner.
 - a. If permission to inspect is denied by the landowner, municipal staff or their designated agent shall secure an administrative inspection warrant from the district or superior court under RSA 595-B Administrative Inspection Warrants. Expenses associated with inspections shall be the responsibility of the applicant/property owner.
 - b. If violations or non-compliance with a condition(s) of approval are found on the site during routine inspections, the inspector shall provide a report to the Planning Board documenting these violations or non-compliance including recommend corrective actions. The Planning Board shall notify the property owner in writing of these violations or non-compliance and corrective actions necessary to bring the

property into full compliance. The Planning Board, at their discretion, may recommend to the Select Board to issue a stop work order if corrective actions are not completed within 10 days.

- c. If corrective actions are not completed within a period of 30 days from the Planning Board or Board notification, the Planning Board may exercise their jurisdiction under RSA 676:4-a Revocation of Recorded Approval.
2. The applicant shall bear final responsibility for the installation, construction, inspection, and disposition of all stormwater management and erosion control measures required by the Planning Board. Site development shall not begin before the Stormwater Management Plan receives written approval by the Planning Board.
3. In the event a property owner refuses to repair infrastructure that is damaged or is not functioning properly, the Town retains the right but not the obligation and accepts no responsibility, to repair or maintain stormwater infrastructure if a property is abandoned or becomes vacant.
4. Landowners shall be responsible for submitting a report to the Planning Department or designated agent by September 1 every two years, with the first report due within two years of the receipt of an Occupancy Permit. The report shall be signed and stamped by a qualified professional engineer of the landowner's choice that all stormwater management and erosion control measures are functioning per the approved stormwater management plan. The report shall note if any stormwater infrastructure has needed any repairs other than routine maintenance and the results of those repairs. If the stormwater infrastructure is not functioning per the approved stormwater management plan the landowner shall report on the malfunction in their report and include detail regarding when the infrastructure shall be repaired and functioning as approved.
5. If no report is filed by September 1 in the year the report is due, the Select Board or their designated agent shall have site access to complete routine inspections to ensure compliance with the approved stormwater management and sediment and erosion control plans. Such inspections shall be performed at a time agreed upon with the landowner.

Table 1. Stormwater Infrastructure Design Criteria (See next page)

| Design Criteria | Description | | | | | | | | | | |
|--|--|------------------|-------------------------|---|------|---|------|---|------|---|------|
| Water Quality Volume (WQV) | $WQV = (P)(R_v)(A)$ P = 1 inch of rainfall R _v = unitless runoff coefficient, $R_v = 0.05 + 0.9(I)$ I = percent impervious cover draining to the structure converted to decimal form A = total site area draining to the structure | | | | | | | | | | |
| Water Quality Flow (WQF) | $WQF = (q_u)(WQV)$ WQV = water quality volume calculated as noted above q _u = unit peak discharge from TR-55 exhibits 4-II and 4-III Variables needed for exhibits 4-II and 4-III: I _a = the initial abstraction = 0.2S S = potential maximum retention in inches = $(1000/CN) - 10$ CN = water quality depth curve number = $1000 / (10 + 5P + 10Q - 10[Q^2 + 1.25(Q)(P)]^{0.5})$ P = 1 inch of rainfall Q = the water quality depth in inches = WQV/A A = total area draining to the design structure | | | | | | | | | | |
| Groundwater Recharge Volume (GRV) | $GRV = (A_i)(R_d)$ A _i = the total area of effective impervious surfaces that will exist on the site after development R _d = the groundwater recharge depth based on the USDA/NRCS hydrologic soil group, as follows: <table style="margin-left: 40px; border: none;"> <thead> <tr> <th style="text-align: left;">Hydrologic Group</th> <th style="text-align: left;">R_d (inches)</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>0.40</td> </tr> <tr> <td>B</td> <td>0.25</td> </tr> <tr> <td>C</td> <td>0.10</td> </tr> <tr> <td>D</td> <td>0.00</td> </tr> </tbody> </table> | Hydrologic Group | R _d (inches) | A | 0.40 | B | 0.25 | C | 0.10 | D | 0.00 |
| Hydrologic Group | R _d (inches) | | | | | | | | | | |
| A | 0.40 | | | | | | | | | | |
| B | 0.25 | | | | | | | | | | |
| C | 0.10 | | | | | | | | | | |
| D | 0.00 | | | | | | | | | | |
| Channel Protection Volume (CPV) | If the 2-year, 24-hour post-development storm volume <u>does not increase</u> due to development then: control the 2-year, 24-hour post-development peak flow rate to the 2-year, 24-hour predevelopment level. If the 2-year, 24-hour post-development storm volume <u>does increase</u> due to development then: control the 2-year, 24-hour post-development peak flow rate to ½ of the 2-year, 24-hour pre-development level or to the 1-year, 24-hour pre-development level. | | | | | | | | | | |
| Peak Control | Post-development peak discharge rates shall not exceed pre-development peak discharge rates for the 10-year, 50-year, 100-year 24-hour storms | | | | | | | | | | |
| EIC and UDC | %EIC = area of effective impervious cover/total drainage areas within a project area x 100 %UDC = area of undisturbed cover/total drainage area within a project area x 100 | | | | | | | | | | |

6.12 OTHER INFRASTRUCTURE

01 SIDEWALKS – Sidewalks shall be provided for pedestrian traffic to provide connection between the main entrances of business, housing or industrial establishments and parking areas. If shoppers or employees are reasonably anticipated, provisions shall be made for sidewalks running from the street line to the establishments. All such sidewalks shall be at

least six inches above the road grade and protected by curbing. The design shall include means for accessibility. Provisions for a school bus stop shall be required in multi-family housing developments, if requested by the Raymond School District.

02 OUTDOOR LIGHTING – Outdoor lighting shall be in compliance with the Town of Raymond Outdoor Lighting Design Standards and shall be so directed and shielded so that no glare will spill out onto residentially-zoned property or cause a safety hazard. After 12:00 midnight, only that amount of lighting necessary for the operation, or security of the premises shall be permitted. Fixture designs, types and locations shall be subject to the approval of the Planning Board. On projects where lighting will be proposed and provides, the applicant shall submit a separate lighting plan.

03 SIGNS – Signs shall be in compliance with the Raymond Zoning Ordinance.

04 SNOW STORAGE – Provisions shall be made for snow storage and/or removal during winter months. Snow shall be removed at least twenty feet from all driveways, intersections and access points. Snow storage locations shall be designated and shown on the site plan.

05 SOLID WASTE STORAGE – All solid waste and recyclable materials shall be stored in containers and/or buildings specifically designed and constructed for that purpose. Waste storage areas shall be screened from view from the adjacent roadways. Solid waste removal is the responsibility of the applicant. Solid waste shall be disposed of at a permitted solid waste facility. The Town of Raymond does not provide solid waste disposal of any kind for developments classified as multi-family or non-residential.

06 UNDERGROUND STORAGE TANKS – All underground storage tanks, regardless of size or type, shall be installed in conformance with New Hampshire Department of Environmental Services Regulations.

07 NOISE LEVELS – Noise emanation from the building or site, as measured outside of the building at the property line, shall at no time exceed five decibels (dBA) over the existing ambient level.

6.13 OTHER CRITERIA

01 SMOKE, AIR CONTAMINATES, PARTICULATE MATTER – The emission of smoke, air contaminates, or particulate matter generated by commercial or industrial uses shall be designed in compliance with New Hampshire Department of Environmental Services Regulations. Dust and other types of airborne matter from sources such as storage areas, yards, roads and driveways shall be reduced to a minimum by appropriate landscaping, screening, paving or other best management practices.

02 HEAT AND GLARE – Any operation producing intense heat and glare shall be conducted within a completely enclosed building, and in such a manner as to not create a public nuisance or hazard along lot boundary lines.

03 STUMPS – All stumps shall be removed from the site unless approval for an on-site stump dump is secured at the time of site plan approval. At a minimum, stumps, rubble and brush shall be transported to a designated area within the development. The waste area shall be located and shown on the approved site plan. Waste areas shall be located above seasonal high ground water, capped with fill, loamed and seeded. All local, State and Federal Regulations pertaining to disposal of stumps and solid waste shall be adhered to. Waste areas shall be subject to the approval of the Planning Board.

04 ODIFEROUS MATTER – Odors shall not be discernible at the property boundaries. A plan for the reduction of odors crossing property boundaries may be required.

05 RADIATION HAZARD – All operations using or storing radioactive materials, whether or not licensed by the United States Nuclear Regulatory Commission (NRC), or the New Hampshire Bureau of Radiological Health, Division of Public Health Services, shall comply with all applicable Regulations of the NRC and the NH Division of Public Health Services, including those Regulations addressing low level radioactive materials.

06 RESTRICTIONS ON PERMITTED USES – All manufacturing, storage and similar uses shall be conducted within the enclosed building. Outside storage is allowed as long as it is screened by either a fence or other approved landscaping.

6.14 TRAFFIC MARKINGS

All parking spaces, stop lines, fire lanes, no-parking zones, lane indicators and such other traffic control pavement markings shall be shown on the approved site plan, and be applied in accordance with the following directions:

01 Pavement markings shall be of latex, reflective traffic paint with a minimum line width of four inches and a minimum dry film thickness of fifteen mils.

02 The following color and width conventions shall apply:

| Description | Number | Color | Width |
|--|--------|--------------------------|------------------|
| Parking stalls; Lane Dividers (one-way traffic) | Single | White | Four Inches |
| Lane Dividers (two-way traffic) | Double | Yellow | Four Inches Each |
| Stop Lines | Single | White | Twelve Inches |
| Descriptive Wording High (i.e. "Fire Lane") | Single | White | Eighteen Inches |
| Handicapped Space Symbol | N/A | White w/ Blue Background | Eighteen Inches |

ARTICLE VII – ADMINISTRATION AND ENFORCEMENT

7.01 PERFORMANCE AGREEMENT AND GUARANTEE

01 As part of the granting of approval, the Planning Board requires the Petitioner to execute a Performance Agreement. The Board also requires an Inspection Escrow be established before any work commences on the site. The Code Enforcement Officer shall not issue any building permits until the Performance Agreement is executed and the Inspection Escrow is established.

02 In the case where a building is proposed, the developer shall provide a Site Plan Performance Bond for any remaining improvements prior to the issuance of a Certificate of Occupancy. The cost of improvements required shall be presented and agreed upon prior to construction, and may be established using either of the following methods:

- a. The applicant provides cost estimates for construction of all the site improvements, only excluding the on-site septic system and occupied buildings. Said cost is to be based upon standard cost preparation guides such as prepared by R.S. Means Company, Inc. and Equipment Guidebook Company, or the average of public sector bid costs for similar work. All costs must be current and/or adjusted for inflation over the anticipated time frame of the project. The applicant's bond must be reviewed and approved by the Town's Review Engineer for accuracy.
- b. The Town's Review Engineer calculates the bond amount using similar methods referred to in item a (above), plus standard cost estimate charts developed for the Town and updated periodically. Said cost estimate charts are available to the applicant for their use in bond calculations as specified in item a (above). Standard applicable costs shall be applied for the Engineer's use.

In either case, a 10% contingency factor shall be added to subtotals of all bond amounts to cover unknown conditions. Also, anticipated cost increase due to inflation during the course of construction must be included.

- c. The Performance Bond shall be one of the following:
 - a. Savings Account, with the Town of Raymond as its sole beneficiary;
 - b. Certificate of Deposit, with the Town of Raymond as its sole beneficiary;
 - c. Cash, with the Town of Raymond as its sole beneficiary;
 - d. Irrevocable Letter of Credit, with the Town of Raymond as its sole beneficiary.

7.02 MAINTENANCE BOND

01 The Board may require surety covering maintenance of improvements for a period of two years from the date of completion in an amount not to exceed 15% of the total cost of said improvements. Amount of surety to be recommended by the Town’s Review Engineer, and approved by the Planning Board. The Town’s Review Engineer’s recommendation shall be based upon his/her knowledge and inspection of the work performed to construct the approved improvements. If repair or unusual maintenance is needed or additional improvements are required, such costs as are necessary shall be drawn against such surety.

7.03 INSPECTION ESCROW

01 All applicants shall be required to deposit an Inspection Escrow with the Town prior to the start of any site improvements. This Escrow shall cover the cost of the Public Works Director or his designee, who shall monitor and inspect improvement for compliance with approved plans and required engineering standards. Payment shall be to the Town Treasurer in an amount approved by the Planning Board which shall be not less than 4% of the site Performance Bond estimate. Interest earned from said Escrow shall be retained by the Town to cover administrative costs.

7.04 PRE-CONSTRUCTION CONFERENCE

01 At least fifteen days prior to commencing construction of any required improvements, the applicant shall post to the Town the Inspection Escrow and shall schedule a Pre- Construction Conference through the Planning and Development Department to coordinate site activities with pertinent Town Departments.

7.05 PROPER INSTALLATION OF IMPROVEMENTS

01 If the Public Works Director or the Planning Board’s designee determines that required improvements have not been constructed in accordance with approved plans and specifications filed by the applicant; or any conditions of the Planning Board approval, he/she shall so report such to the Planning and Development Department. The Public Works Director shall also notify the applicant and, if necessary, the bonding company or escrow agent, and take all necessary steps to preserve the Town’s rights under the bond or agreement. No plan shall be approved by the Planning Board on the same parcel as long as the applicant is in default on a previously approved site plan.

02 It shall be the responsibility of the applicant or their agent to provide the Public Works Director or his designee with materials testing information, performed by a testing laboratory acceptable to the Public Works Director or his designee, attesting to compliance of all improvement materials incorporated into the development. Said compliance tests shall be required, but not be limited to the following:

- a. Calculations and proctor analysis of all gravel, sands and select materials;
- b. In place density testing of all gravel, sands and select materials;
- c. Mix design and compressive strength tests for concrete;

- d. Extraction, gradation and compaction tests for all bituminous asphalt;
- e. All additional testing, which the Public Works Director or his designee determines is necessary to assure compliance with local, State and Federal Regulations.
- f. Construction of all multi-family and non-residential site plan improvements shall be in general accordance with the Town of Raymond Subdivision Regulations titled Road Construction Standards.

7.06 RELEASE OR REDUCTION OF PERFORMANCE BOND

- 01** The Board of Selectmen and Planning Board will not accept dedication of required public improvements, nor release or reduce a Performance Bond until the Public Works Director or his designee has submitted a certificate stating that all required improvements have been satisfactorily completed, and until the applicant’s engineer or surveyor has certified to the Town’s Review Engineer, through submission of detailed “as-built” plans indicating locations, dimensions, materials and other information required by the Planning Board or Town’s Review Engineer, that the layout of the line and grade of all public improvements is in accordance with the site plan and construction plans for the development.
- 02** In addition, Performance Bond Reduction shall only be performed upon total completion of each of the following major construction milestones:
 - a. Layout, limits and erosion protection
 - b. Clearing and grubbing
 - c. Site sub grade (completion of cuts and fills)
 - d. Drainage
 - e. Utility completion (all water, electric, etc. installed and accepted)
 - f. Granular materials
 - g. Asphalt binder completion (all foundation materials and asphalt binder course installed and accepted)
 - h. Guard rails and fencing
 - i. Landscaping, loam, seed and mulch
 - j. Substantial completion* (development is ready to function for intended purpose and all improvements to this point are acceptable)
 - k. Final inspection (all proposed improvements are fully completed and accepted)

* The applicant must have substantial completion approval from the Public Works Director or his designee in order to apply for occupancy permits from the Town.
- 03** Development may be constructed in phases, only if approved by the Planning Board at the time of plan approval.

7.07 OCCUPANCY

- 01** No development may be occupied or used unless a certificate of occupancy has been issued by the Code Enforcement Officer.
- 02** The Code Enforcement Officer shall not issue a building permit until these Regulations have been complied with, and the improvements have been completed or a Performance Bond has been provided to the Town for unfinished improvements.
- 03** Development of a phase of the development must be at substantial completion for that phase in order to receive a certificate of occupancy.

7.08 WAIVERS

- 01** Where the Planning Board finds that unnecessary hardship may result from strict compliance with these regulations with respect to a particular tract of land, the Board may modify or waive these regulations so that substantial justice may be done and the public interest is secured, provided that:
 - a. The granting of the waiver will not be detrimental to public safety, health, or welfare or injurious to other adjacent property;
 - b. The waiver shall not have the effect of nullifying the intent and purpose of these regulations, the Zoning Ordinance, Master Plan or Official Zoning Map;
 - c. In granting waivers, the Planning Board may require such conditions as will, in the Board's judgment, secure substantially the objectives of the standards or requirements of these regulations;
 - d. A petition for waiver shall be submitted by the applicant at the time when the application is filed for consideration by the Planning Board. All petitions shall be made in writing using the Town's Waiver Request Form. The petition shall state fully the grounds for the waiver and all of the facts relied upon by the petitioner.
 - e. The Planning Board formally votes on such waiver request(s); and
 - f. Any granted waivers are noted on the final approved plan.
- 02** Pursuant to RSA 674:44(III)(e), the Planning Board may only grant a waiver if it finds by majority vote that:
 - a. Strict conformity would pose an unnecessary hardship to the applicant and waiver would not be contrary to the spirit and intent of the regulations; or
 - b. Specific circumstances relative to the site plan, or conditions of the land in such site plan, indicate that the waiver will properly carry out the spirit and intent of the regulations.

7.09 PENALTIES AND FINES

Any violation of these Regulations shall be subject to a civil fine or criminal penalty as provided in NH RSA 676:17, as amended. The Board of Selectmen or the Code Enforcement Officer are hereby designated as the proper local authorities of the Town to institute appropriate action under the provision of RSA 676:17.

7.10 OTHER REGULATIONS

Wherever these Regulations are in conflict with other local, State or Federal Ordinances, the more stringent shall apply.

7.11 VALIDITY

If any section, part of a section or paragraph of these Regulations shall be declared invalid or unconstitutional, it shall not be held to invalidate or impair the validity, force or effect of any other section, part of a section or paragraph of these Regulations.

7.12 ADOPTION & AMENDMENT HISTORY

The Town of Raymond Site Plan Review Regulations were adopted by a majority vote of the Planning Board following a duly noticed public hearing. These Regulations supersede all sections of the previous Site Plan Review Regulations.

AMENDMENT HISTORY

- 05/24/1990
- 07/13/2000
- 03/06/2012
- 01/16/2014
- 10/03/2019
- 10/6/2022
- 05/9/2024

7.13 AS AMENDED DISCLAIMER

All instances of a cited RSA or Published Document shall be understood to encompass any subsequent legal changes or updates, typically written “as amended”. However, the omission of the wording shall not preclude the intent to adhere to the most current version of an RSA or Published Document.

Appendix I - Change of Use Review

1. Each change of use request must be accompanied by an application fee as defined in Appendix 2, entitled "Site Plan Review Fees".
2. Uses allowed are only those uses permitted in the appropriate zones under Article 4 of the Raymond Zoning Ordinance, entitled "Allowed Uses".
3. A change of use requiring Planning Board review shall be determined by the Code Enforcement Officer in consultation with the Planning Board. The determination will be based on the following:
 - a) Does the proposed activity reflect the nature of the existing or former use?
 - b) Is any proposed use different in character, nature and kind from the existing use?
 - c) Is any proposed use having a substantially different impact on the neighborhood?
 - d) Any change of use which, in the opinion of the Code Enforcement Officer that requires Planning Board approval in order to ensure the health, welfare, morality, (integrity, principles) and safety of Raymond's citizens and recreational guests.
4. Proposals for Change of Use Review must include the following information:
 - a) Present use and proposed use of the property.
 - b) Present and proposed parking facilities.
 - c) A scaled plan of the property showing street frontage, building location, parking, driveways, traffic flow, loading spaces and walkways.
 - d) Location, description and size of existing and/or proposed signs.
 - e) Physical changes to the exterior of the structure including color changes and lighting.
 - f) An operational plan listing proposed hours of operation both open and closed to the public.
5. The Planning Board may request any further information it deems necessary for proper review of the change of use request and shall not take action until such time that the information is provided to the Board.

Appendix II - Site Plan Review Fees

Please find the most current fee schedule at the Town Hall

Appendix III- Site Plan Review Checklist

Town of Raymond, NH

PROJECT NAME: _____ APPLICANT NAME: _____ DATE RECEIVED: _____
 MAP#: _____ LOT #: _____ APPLICATION DATE: _____ APPLICATION #: _____

A copy of all plans and technical reports must be sent to the Planning and Development Department. Proof of submittal must be provided to the Planning and Development Department at the time of application. If proof of transmittal is not provided, the application may be delayed until the following month's Planning Board meeting.

| SUBMITTED | | | WAIVER REQUESTED | |
|--------------------------|--------------------------|--|--------------------------|--------------------------|
| YES | NO | | YES | NO |
| <input type="checkbox"/> | <input type="checkbox"/> | 1. Name of project; names and addresses and letters of authorization of all owners of record; Tax Map and Lot Number. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 2. Name, license number and seal of surveyor, architect, landscape architect, or other design professional; north arrow, scale, and date of plan; signature block of 4 inches (long) by 2 inches (wide). | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 3. The zoning district the project is located, vicinity map and zoning district(s) of all parcels within the application. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 4. Abutters and uses of abutting land within 200 feet of the site. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 5. Shape, size, height, location, and use of existing and proposed structures located on the site and within 200 feet of the site. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 6. Boundary lines, dimensions, and bearings; lot(s) area in acres and square feet and a calculation of the total disturbed area in square feet. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 7. Location, name, and widths of any existing and proposed roads on the property and within 200 feet of the site. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 8. Location of all existing and proposed sidewalks and driveways, with indication of the direction of travel for both pedestrian and vehicular traffic. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 9. All proposed access points to the site, sight distance at access point(s), curb cuts (existing or proposed), and any proposed changes to existing streets; copy of driveway permit. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 10. Location and number of parking spaces (including ADA accessible spaces) and loading spaces. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 11. Location, type, and nature of all existing and proposed landscaping and screening, including size. Include an Invasive Species checklist and plan designation of NH Native Species. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 12. Location, type, and nature of all existing and proposed exterior lighting and show the illumination rate in footcandles. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 13. All natural features within the site (streams, ponds, vernal pools, wetlands, etc.) (If there is Zone G land the conservation committee must be notified) | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 14. Waste/dumpster locations and elevations of their enclosures and snow storage areas. | <input type="checkbox"/> | <input type="checkbox"/> |

- | | | | | |
|--------------------------|--------------------------|--|--------------------------|--------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | 15. Existing and proposed grades and contour lines, including Base Flood Elevation (BFE) where appropriate. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 16. Size and location of all existing and proposed water mains, sewers, culverts, and distances to the existing fire hydrants, cisterns and/or fire ponds. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 17. Copy of certification from licensed septic designer as to sufficiency of the OSTDS. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 18. Location and type of proposed wastewater disposal system; outline of 4,000 sq. ft. area; test pits; record of percolation tests. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 19. Existing and proposed stormwater drainage system. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 20. Location of existing and proposed on-site wells (showing required radii on the property). | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 21. Soil survey data (see: requirements for soils and wetlands data). | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 22. Location and dimensions of any existing or proposed easements, deed restrictions, covenants, or other encumbrances upon the lot(s). | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 23. Information about any hazardous issues or conditions within the subject property or adjacent properties known to the application prior to the application. (ie. Phase 1) | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 24. Copy of the NHDES OSTDS application, if applicable. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 25. NHDES Alteration of Wetlands Application or Permit, if applicable | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 26. NHDES Alteration of Terrain Application or Permit, if applicable | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 27. NHDOT Driveway Application or Permit, if applicable. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 28. All state applications related to underground storage tanks (USTs). | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 29. Army Corps of Engineers (ACOE) Application or Permit, if applicable. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 30. Written narrative summarizing the project, separate from the site plan pages themselves. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 31. Copy of all submitted materials submitted on a thumb drive or sent to the Town of Raymond via Dropbox link or other filesharing method. | <input type="checkbox"/> | <input type="checkbox"/> |
| | | OTHER: | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 1. Any other federal, state, or local permits. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 2. Building elevations (in color and of all four sides) and depiction of overall design. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 3. Proposed sign location, size, height, and design | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 4. Such additional studies as may have been required by the Planning Board during Conceptual or Design Review or through the Technical Review Committee. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 5. Twelve (12) full-size copies (24 x 36) of all plans and six (6) copies of all plans in 11 X 17 format, and digital copy of plans. | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 6. Eight (8) copies of all studies. | <input type="checkbox"/> | <input type="checkbox"/> |

FEES:

- | | | | | |
|--------------------------|--------------------------|---|--------------------------|--------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | 1. Application Fees | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 2. Abutter Notice Fees (include three (3) labels per abutter) (\$10.00 per abutter) | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 3. Engineering and Legal Escrow | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | 4. Site Review-Administrative Fee | <input type="checkbox"/> | <input type="checkbox"/> |

Name of the person completing the Checklist: _____

Signature: _____ Date Prepared: _____